


WELL LOG BUREAU - KANSAS GEOLOGICAL SOCIETY.
412 Union National Bk Bldg., Wichita, Kansas.

50308

CARTER OIL CO.
J.F. Whitford No. 1.

SEC. 12 T. 7 R. 17W
NEc SE
455'S 440'W NEcSE $\frac{1}{4}$

County. Rooks



Elevation.

Production. Dry

Total Depth. 3355' P.B. 2855
Comm. 5-3-38 Comp. 6-1-38
Shot or Treated. 3000, 1000 & 1000 Gals.
Contractor. Co. Tools
Issued. 7-23-38 Rotary 3355

CASING:
85/8" 529'
41/2" 2932'

Figures Indicate Bottom of Formations.

gravel & blue shale	75	shale & shells	2327	porous, good sh oil 2675-85
shale	210	shale & brkn lime	2375	partly porous 2680-95
shale & shells	353	sdv shale	2447	dolomite porous 2715-30
shale	390	shale & shells	2495	porous, dead oil stain 2835-46
sand	440	lime	2529	<u>oolitic show oil 2940</u>
shale	450	shale	2540	<u>oolitic show oil 2900</u>
sand	470	brkn lime & shale	2581	<u>oolitic slight sh oil-</u>
shale	501	shale & shells	2629	trace oolites 2980-3010
shale & shells	531	shale	2640	<u>oolitic-very slight sh</u>
shale	675	lime	2670	<u>oil 3070</u>
sand	825	cored lime	2675	porous 3140
shale	895	lime	2741	shot with 83 shots 2932-2940
shale red	926	shale	2750	got just rainbow of <u>oil</u> .
sand & shale	995	lime	2775	shot 24 more shots from
sdv shale	1030	lime & shale brks	2785	2932-2940 got just a
shale & shells	1100	lime	2870	rainbow of <u>oil</u> . Perforated
sdv lime & shale	1130	brkn lime	2891	with 36 shots 2893-2902
anhydrite	1170	lime	2898	acidized with 250 gal. no show.
shale red	1210	cored lime	2903	Re-Acidized with 3000 gal
shale red & blue	1354	lime	2920	showed 1 gal oil and no wtr
shale	1375	brkn lime	2934	every 2 hours.
shale & shells	1420	lime	2935	P.B. from 2940 shot with
brkn lime	1430	cored lime	2951	108 shots 2657-2675. 1000 gal.
shale	1500	lime	3126	P.B. 2855 1000 gal acid
brkn lime	1532	shale	3137	2657-2675 test showed 1 gal
shale & lime	1622	lime	3155	<u>oil</u> and some water every
shale & shells	1640	lime & shale	3179	2 hours.
brkn lime	1660	shale	3258	bailed down tested 5 hours.
shale	1680	shale & chert	3297	made 3/4 bbls water and a
shale & shells	1683	conglomerate	3314	rainbow of oil.
lime	1700	shale & chert	3321	
shale	1746	lime	3355	
brkn lime	1794	Total Depth.		
brkn lime & shale	1850			
shale	1900	Topeka 2640-2875		
shale & shells	1915	Lans. K.C. 2875-3254		
lime	1930	congl. 3254-3321		
shale & lime shells	2000	Arbucklo 3321-3355		
shale & shells	2020			
lime	2050			
shale & shells	2090			
sand	2100			
brkn lime	2142			
shale & shells	2226			
shale	2292			