

KANSAS

WELL COMPLETION REPORT AND  
DRILLER'S LOGState Geological Survey  
WICHITA BRANCH

API No. 15

Rooks

County

Number

Operator

Rumail Co

Address

512 S. Wyoming Junction Kansas 67663

Well No.

3

Lease Name

Brufflith

Footage Location

330

feet from (N) line

990

feet from (W) line

Principal Contractor

Ranger Drilling Co Inc.

Geologist

Eric Waddell

Spud Date

3-23-81

Date Completed

3-28-81

Total Depth

3277

P.B.T.D.

Directional Deviation


Oil and/or Gas Purchaser

C. R. H. Inc.

S. 30 T. 7 R. 17 W

Loc. NE NW NE

County Rooks

640 Acres  
N

Locate well correctly

Elev.: Gr. 1779

DF 1782 KB 1784

## CASING RECORD

Report of all strings set — surface, intermediate, production, etc.

Purpose of string	Size hole drilled	Size casing set (in O.D.)	Weight lbs/ft.	Setting depth	Type cement	Sacks	Type and percent additives
Surface	12 1/4	8 5/8	20	1220	60/40 Poz	450	2% gel 3% CC
Long String	7 7/8	5 1/2	14	3273	Common	135	10% Salt

## LINER RECORD

## PERFORATION RECORD

Top, ft.	Bottom, ft.	Sacks cement	Shots per ft.	Size & type	Depth interval

## TUBING RECORD

Size	Setting depth	Packer set at			

## ACID, FRACTURE, SHOT, CEMENT SQUEEZE RECORD

Amount and kind of material used	Depth interval treated
Swabbed 15 bbl oil natural no water Per hr,	

## INITIAL PRODUCTION

Date of first production 4-16-81		Producing method (flowing, pumping, gas lift, etc.) pumping			
RATE OF PRODUCTION PER 24 HOURS		Oil 70	Gas none	Water none	Gas-oil ratio none
		bbls.	MCF	bbls.	CFPB
Disposition of gas (vented, used on lease or sold)				Producing interval(s) Arb-3273-78 open hole	

INSTRUCTIONS: As provided in KCC Rule 82-2-125, within 90 days after completion of a well, one completed copy of this Drillers Log shall be transmitted to the State Geological Survey of Kansas, 4150 Monroe Street, Wichita, Kansas 67209. Copies of this form are available from the Conservation Division, State Corporation Commission, 245 No. Water, Wichita, Kansas 67202. Phone AC 316-522-2206. If confidential custody is desired, please note Rule 82-2-125. Drillers Logs will be on open file in the Oil and Gas Division, State Geological Survey of Kansas, Lawrence, Kansas 66044.

Operator		DESIGNATE TYPE OF COMP.: OIL, GAS, DRY HOLE, SWDW, ETC.:
Well No.	Lease Name	
S _____ T _____ R _____ E _____ W		

### WELL LOG

Show all important zones of porosity and contents thereof; cored intervals, and all drill-stem tests, including depth interval tested, cushion used, time tool open, flowing and shut-in pressures, and recoveries.

SHOW GEOLOGICAL MARKERS, LOGS RUN,  
OR OTHER DESCRIPTIVE INFORMATION.

FORMATION DESCRIPTION, CONTENTS, ETC.	TOP	BOTTOM	NAME	DEPTH
<p>USE ADDITIONAL SHEETS, IF NECESSARY, TO COMPLETE WELL RECORD.</p>				

Date Received	<i>Remick Co</i> Signature	
	<i>Lane Monroe</i> Title	
	<i>Owner</i> Date	
	7-9-81	

# RANGER DRILLING COMPANY, INC.

P.O. Box 717  
Hays, Kansas 67601  
913/625-4210

30-7-17W

State Geological Survey  
WICHITA, BRANCH

## DRILLERS LOG

OPERATOR: Rim Oil Company  
512 So. Wyoming St.  
Plainville, Kansas 67663

CONTRACTOR: Ranger Drilling Company, Inc.  
P.O. Box 717  
Hays, Kansas 67601

LEASE: Griffith WELL: #3

LOCATION: NE/4 NW/4 NE/4  
Section 30-7S-17W  
Rooks County, Kansas

Total Depth: 3275'

Elevation:

Commenced: 3-21-81

Completed: 3-28-81

Casing: 8-5/8" @ 1215'

Status: Pending

RECEIVED  
STATE CORPORATION COMMISSION

APR 21 1981

CONSERVATION DIVISION  
Wichita Kansas

## DEPTHS & FORMATIONS

(All measurements from K.B.)

Surface soil & clay	220	Shale & shells	1980
Sand & shale	603	Shale	2165
Shale	720	Shale & lime	2713
Sand	912	Topeka	2824
Red bed & shale	1100	Lime	2950
Sand, shale & red bed	1205	Lime & shale	3185
Anhydrite	1250	Lime	3275
Shale & lime	1365	T.D.	3275

STATE OF KANSAS )

ss.

COUNTY OF ELLIS )

I, William A. Spivey, of the Ranger Drilling Company, Inc. state  
that the above and foregoing is a true and correct log of the above captioned  
well.

*William A. Spivey*