

State Geological Survey

KANSAS DRILLERS LOG

WICHITA BRANCH

API No. 15

JUN 8 0 REC'D

County

Number

Operator

Rim Oil Company

Address

512 South Wyoming, Plainville, Kansas 67663

Well No.

#1

Lease Name

RIFFE

Footage Location

990

feet from (N) (S) line

330

feet from (E) (W) line

Principal Contractor

John O. Farmer, Inc.

Geologist

Dick Green

Spud Date

4-17-78

Total Depth

3297'

P.B.T.D.

3287

Date Completed

4-27-78


Oil Purchaser

CRA Inc.

S. 30 T. 7S R. 17W E

Loc. SE NE NW

County Rooks

640 Acres
N

Locate well correctly

Elev.: Gr.

1762'

DP 1765'

KB 1767'

CASING RECORD

Report of all strings set — surface, intermediate, production, etc.

Purpose of string	Size hole drilled	Size casing set (in O.D.)	Weight lbs./ft.	Setting depth	Type cement	Sacks	Type and percent additives
Surface	12-1/4	8-5/8	26	1172'	Common	475	
Production	7-7/8	4-1/2	10-1/2	3296'	Common	175	

LINER RECORD

PERFORATION RECORD

Top, ft.	Bottom, ft.	Sacks cement	Shots per ft.	Size & type	Depth interval
			Two	Golden Jet #	4 3234-75
			Two	" "	" 2919-23
TUBING RECORD					
Size	Setting depth	Packer set at			
2"	3272				

ACID, FRACTURE, SHOT, CEMENT SQUEEZE RECORD

Amount and kind of material used	Depth interval treated
1500 Gal. Reg.15%	3234-3275
1000 Gal. Reg.15% & 1000 Gal. C.R.A.	2919-2923

INITIAL PRODUCTION

Date of first production	Producing method (flowing, pumping, gas lift, etc.)				
5-22-78	Pumping				
RATE OF PRODUCTION PER 24 HOURS	Oil	Gas	Water	Gas-oil ratio	
	9 bbl.		None	bbls.	CFPB
Disposition of gas (vented, used on lease or sold)			Producing interval (s)		

INSTRUCTIONS: As provided in KCC Rule 82-2-125, within 90 days after completion of a well, one completed copy of this Drillers Log shall be transmitted to the State Geological Survey of Kansas, 4150 Monroe Street, Wichita, Kansas 67209. Copies of this form are available from the Conservation Division, State Corporation Commission, 3830 So. Meridian (P.O. Box 17027), Wichita, Kansas 66217. Phone AC 316-522-2206. If confidential custody is desired, please note Rule 82-2-125. Drillers Logs will be on an open file in the Oil and Gas Division, State Geological Survey of Kansas, Lawrence, Kansas 66044.

Operator Rim Oil Company		DESIGNATE TYPE OF COMP.: OIL, GAS, DRY HOLE, SWDW, ETC.:
Well No. 1	Lease Name RIFFE	Oil
s 30 T 7S R 17W _W		

WELL LOG

Show all important zones of porosity and contents thereof; cored intervals, and all drill-stem tests, including depth interval tested, cushion used, time tool open, flowing and shut-in pressures, and recoveries.

SHOW GEOLOGICAL MARKERS, LOGS RUN, OR OTHER DESCRIPTIVE INFORMATION.

FORMATION DESCRIPTION, CONTENTS, ETC.	TOP	BOTTOM	NAME	DEPTH
Shale & Sand -0- 370				
Sand 370 400				
Shale & Sandstone 400 675				
Sand 675 869				
Red Bed 869 1166				
Anhydrite 1166 1205				
Shale 1205 1430				
Shale & Lime 1430 2680				
Lime & Shale 2680 2985				
Lime 2985 3160				
Lime & Shale 3160 3235				
Chert & Arb 3235 3290				
Arb 3290 3297				

USE ADDITIONAL SHEETS, IF NECESSARY, TO COMPLETE WELL RECORD.

Date Received	<i>John O. Lammert</i> Signature President Title May 5, 1978 Date
---------------	---