

35-7-17W


WELL LOG BUREAU KANSAS GEOLOGICAL SOCIETY
412 Union National Bk Bldg., Wichita, Kansas

Company **AIKAY OIL CO.**
Farm **Hindman** No. **1**

SEC. **35** T. **7** R. **17W**
NW 1/4 NE

Total Depth. **2713**
Comm. **5-18-46** Comp. **5-29-46**
Shot or Treated. **Acidized**
Contractor.
Issued. **9-21-46**

County. **Rooks**
KANSAS



Elevation. _____

Production. Pot. **107 Bbls. oil**
Plus **22 % wtr.**

Figures Indicate Bottom of Formations.

CASING:
10 3/4" 1155' Cem.
7" 2693' Cem.

shale	250
shale & shells	385
sand & shale	530
shale	570
shale & shells	628
sand	635
shale	646
sand & shale	657
sandy shale	675
shale	690
sand & shells	870
red rock & shale	935
shale sdy	970
red rock & shale	1145
Anhydrite	1180
Anhydrite & Lime	1200
shale	1230
shale, sand lime, & Pyrite	1365 ✓
shale & shells	1440
shale sdy	1655
lime & sdy shale	1765
lime & shale	2055
shale & shells	2095
lime & shale	2295
shale & shells	2230
shale	2481
lime	2505
shale	2520
lime	2560
shale & lime	2565
lime	2590
lime & shale	2627
sand & shale	2667
sand	2671
lime grey	2695
lime sft	2704
Good Sat. poor Por.	
lime hd	2713
Total Depth	

1835
1145
7690

Tops:
Topeka 2671

Drilled plug & cleaned
out to bottom. Set 17 hrs.
& had 6 B' & 230'
oil. Set 40 hrs.--showed 5
B' & 375' oil.

Acidized with total of
4500 Gal. of acid in three
treatments of 1300, 1600
and 1600 Gal.

Pay 2695-2704'