

KANSAS GEOLOGICAL SOCIETY
 KANSAS WELL LOG BUREAU - KANSAS WELL SAMPLE BUREAU
 KANSAS GEOLOGICAL SOCIETY BUILDING
 508 EAST MURDOCK - WICHITA, KANSAS


15-163-20055

COMPANY J. MARK RICHARDSON
 FARM Bray (twin) NO. 1

SEC. 35 T. 7 R. 18W
 LOC. NE NE SE

TOTAL DEPTH 3400
 COMM. 8-7-67 COMP. 8-15-67
 SHOT OR TREATED
 CONTRACTOR Gabbert-Jones
 ISSUED 4-20-68

COUNTY Rooks
 KANSAS



CASING
 20 10
 15 8 5/8" @ 200' w/140 SX
 12 S
 13 4 1/2" @ 3392' w/100 SX

ELEVATION 1908' KB
 PRODUCTION 75 BOPD, NW
 ARB 3393-99

FIGURES INDICATE BOTTOM OF FORMATIONS

DEPTH	FORMATION	REMARKS
FROM To		
0 140	ROCK	
140 200	CLAY AND SHALE	RAN 11 JOINTS 8-5/8" CASING, SET @ 200' w/140 BAGS CEMENT.
200 410	SHALE AND SHELLS	
410 430	SAND	TOBS: SCOUT
430 545	SHALE	
545 555	SAND	
555 950	SHALE AND SAND	Topeka 2831
950 1300	SHALE AND RED BED	Heebner 3040
1300 1335	ANHYDRITE	Toronto 3062
1335 1560	SHALE AND SHELLS	Lansing 3082
1560 1810	SHALE	Base Kansas City 3304
1810 1960	LIME AND SHALE	Marmaton 3334
1960 2140	LIME	Arbuckle 3360
2140 2290	SHALE	
2290 2535	LIME AND SHALE	
2535 2960	SHALE	
2960 3130	LIME AND SHALE	
3130 3305	LIME	
3305 3330	SHALE	
3330 3370	CONGLOMERATE	
3370 3400	LIME	
TD		RAN 106 JOINTS 4 1/2" CASING, SET @ 3392' w/100 BAGS CEMENT.

I, E. E. HALL, CERTIFY THIS IS A CORRECT COPY OF THE DRILLERS' LOG FOR THE WELL DRILLED IN THE APPROX. NE NE SE SECTION 35-79-18W, ROOKS COUNTY, KANSAS, TO THE BEST OF MY KNOWLEDGE AND BELIEF.

E. E. Hall
 E. E. HALL

STATE OF KANSAS

)
) SS