

JAN 3 1970

GABBERT-JONES, INC.
WICHITA, KANSAS
DRILLERS' WELL LOG

36-7-18W

15-163-20204

36-7-18W
SW SW NW

lev. 1840KB

FLINT #1
SW SW NW Section 36-7S-18W
Rooks County, Kansas

Commenced: October 27, 1969
Completed: November 4, 1969

OPERATOR - J. Mark Richardson

DEPTH		FORMATION	REMARKS
From	To		
0	215	Surface soil and shale	Ran 10 joints 8-5/8" casing, set @ 215' w/150 sacks cement.
215	500	Shale and shells	
500	660	Sand and shale	
660	900	Sand	
900	960	Sand and red bed	
960	1233	Shale and shells	
1233	1277	Anhydrite	
1277	1445	Shale	
1445	1550	Shale and shells	
1550	2000	Shale and lime	
2000	2125	Lime	
2125	2970	Lime and shale	
2970	3110	Lime	
3110	3271	Lime and shale	
3271	3325	Lime	
3325	TD		Ran 103 joints 4-1/2" casing, set @ 3324-1/2" w/100 sacks cement. DV Tool @ 1261' w/450 sacks cement.

oil

ank 1241

ank 3297



3334 DDTD

I, E. E. HALL, certify this is a correct copy of the Drillers' Log for the well drilled in the SW SW NW Section 36-7S-18W, Rooks County, Kansas, to the best of my knowledge and belief.

E. E. Hall

E. E. HALL

STATE OF KANSAS)
) SS
COUNTY OF SEDGWICK)

Before me, the undersigned, a Notary Public within and for said County and State, on this 6 day of November, 1969, personally appeared E. E. Hall to me personally known to be the identical person who executed the within and foregoing instrument and acknowledged to me that he executed the same as his free and voluntary act and deed for the uses and purposes therein set forth.

IN WITNESS WHEREOF, I have hereunto set my hand and official seal the day and year last above written.

Barbara A. Lutz