

11/19/82  
TIGHT ~~KCC~~  
P. [Signature]

TYPE  
SIDE ONE

AFFIDAVIT OF COMPLETION FORM

ACO-1 WELL HISTORY

36-7-18W

Two (2) copies of this form shall be filed with the Kansas Corporation Commission, 200 Colorado Derby Building, Wichita, Kansas 67202, within thirty (30) days after the completion of a well, regardless of how the well was completed.  
X Attach separate letter of request if the information is to be held confidential. If confidential, only file one copy. Information on Side One will be of public record and Side Two will then be held confidential.

Applications must be made on dual completion, commingling, salt water disposal, injection and temporarily abandoned wells.

C X Attach one copy only wireline logs (i.e. electrical log, sonic log, gamma ray neutron log, etc.). (Rules 82-2-105 & 82-2-125) KCC# (316) 263-3238.

LICENSE # 5313 EXPIRATION DATE June 30, 1983

OPERATOR F & M OIL CO., INC. API NO. 15-163-21,838

ADDRESS 422 Union Center WICHITA, KANSAS 67202 COUNTY Rooks FIELD

\*\* CONTACT PERSON R. D. Messinger PROD. FORMATION PHONE (316)262-2636

PURCHASER LEASE Kansas "B"

ADDRESS WELL NO. 1

WELL LOCATION SE NW NE

DRILLING Union Drilling Co., Inc. 990 Ft. from North Line and

CONTRACTOR 422 Union Center 1650 Ft. from East Line of the NE (Qtr.) SEC 36 TWP 7S RGE 18W(W).

PLUGGING Union Drilling Co., Inc. WELL PLAT (Office Use Only)

CONTRACTOR 422 Union Center KCC

ADDRESS WICHITA, KANSAS 67202 KGS

TOTAL DEPTH 3523' PBTB SWD/REP

SPUD DATE 11-8-82 DATE COMPLETED 11-19-82 PLG.

ELEV: GR 1925' DF 1932' KB 1935'

DRILLED WITH (CABLE) (ROTARY) (AIR) TOOLS.

DOCKET NO. OF DISPOSAL OR REPRESSURING WELL BEING USED TO DISPOSE OF WATER FROM THIS LEASE


RELEASED  
Date: JAN 1 1984  
FROM CONFIDENTIAL

Amount of surface pipe set and cemented 325'w/475 sxs DV Tool Used? None

THIS AFFIDAVIT APPLIES TO: (Circle ONE) - Oil, Gas, Shut-in Gas, Dry, Disposal, Injection, Temporarily Abandoned, OWWO. Other

ALL REQUIREMENTS OF THE STATUTES, RULES AND REGULATIONS PROMULGATED TO REGULATE THE OIL AND GAS INDUSTRY HAVE BEEN FULLY COMPLIED WITH.

State Geological Survey  
WICHITA BRANCH

A F F I D A V I T

CONFIDENTIAL

R. D. Messinger, being of lawful age, hereby certifies that:

I am the Affiant, and I am familiar with the contents of the foregoing Affidavit. The statements and allegations contained therein are true and correct.

[Signature]  
(Name)

SIDE TWO

ACO-1 WELL HISTORY (H)  
(W)

OPERATOR F & M OIL CO., INC. LEASE Kansas "B" #1 SEC. 36 TWP. 7S RGE 18W

*Wells*

FILL IN WELL INFORMATION AS REQUIRED: WELL NO. \_\_\_\_\_

Show all important zones of porosity and contents thereof; cored intervals, and all drill-stem tests, including depth interval tested, cushion used, time tool open, flowing and shut-in pressures, and recoveries.

SHOW GEOLOGICAL MARKERS, LOGS RUN, OR OTHER DESCRIPTIVE INFORMATION.

FORMATION DESCRIPTION, CONTENTS, ETC.	TOP	BOTTOM	NAME	DEPTH
Check if no Drill Stem Tests Run.			Sample Tops:	
DST#1 3066-3105', 30-45-30-45, wk blow died in 17", flushed tool on 2nd open, no help, rec 20' mud, IFP 36-43#, ISIP 43#, FFP 43- 43#, FSIP 43#, BHT 92°.			Stotler	2657(- 722)
			Tarkio	2705(- 770)
			Howard	2783(- 848)
			Topeka	2851(- 916)
			Heebner	3064(-1129)
			Toronto	3087(-1152)
			Lansing	3106(-1171)
			B/KC	3329(-1300)
			Marmaton	3362(-1400)
			Arbuckle	3388(-1453)
			RTD	3523(-1588)
DST#2 3328-3390', 30-45-30-35, wk blow died in 12", flushed tool 2nd open, no help, rec 25' mud w/oil stains, IFP 57-57#, ISIP 231#, FFP 57-57#, FSIP 123#, BHT 101°.			Electric Log Tops:	
			Anhydrite	1319(+ 6)
			B/Anhydrite	1354(+ 581)
DST#3 3390-3410', 30-45-30-45, wk blow died in 28", flushed tool 2nd open, no help, rec 30' mud w/ few oil spks, IFP 28-28#, ISIP 210#, FFP 36-43#, FSIP 1087#.			Stotler	2658(- 723)
			Tarkio	2706(- 771)
			Howard	2786(- 851)
			Topeka	2855(- 920)
			Heebner	3067(-1132)
			Toronto	3091(-1150)
			Lansing	3111(-1170)
			B/KC	3330(-1395)
			Marmaton	3363(-1428)
			Arbuckle	3392(-1452)
			LTD	3525(-1590)
DST#4 3393-3420', 30-45-30-45, wk blow died in 10", flushed tool 2nd open, no help, rec. 40' mud w/show of oil in tool, IFP 36-36#, ISIP 943#, FFP 36-plugged, FSIP 1001#, BHT 120°.				
DST#5 3411-3435', 30-45-60-45, wk blow died in 8", flushed tool on 2nd opn & got wk blow throughout, rec 60' mud w/oil spks in tool, IFP plugged, ISIP 1173#, FFP 88-89#, FSIP 778#, BHT 98°.				

If additional space is needed use Page 2, Side 2

Report of all strings set — surface, intermediate, production, etc. CASING RECORD (New) or (Used)

Purpose of string	Size hole drilled	Size casing set (in O.D.)	Weight lbs/ft.	Setting depth	Type cement	Sacks	Type and percent additives
Surface	12 1/4"	8-5/8"	24#	365'	Lite Common	350 125	6% gel, 3% CC 3% CC, 2% Gel

LINER RECORD

PERFORATION RECORD

Top, ft.	Bottom, ft.	Sacks cement	Shots per ft.	Size & type	Depth interval

TUBING RECORD

Size	Setting depth	Pecker set at

P

SIDE TWO (Page Two)

ACO-1 WELL HISTORY

OPERATOR F & M OIL CO., INC. LEASE NAME Kansas "B" #1 SEC. 36 TWP. 7S RGE. 18W

FILL IN WELL LOG AS REQUIRED:

Show all important zones of porosity and contents thereof; cored intervals, and all drill-stem tests, including depth interval tested, cushion used, time tool open, flowing and shut-in pressures, and recoveries.

SHOW GEOLOGICAL MARKERS, LOGS RUN, OR OTHER DESCRIPTIVE INFORMATION.

FORMATION DESCRIPTION, CONTENTS, ETC.	TOP	BOTTOM	NAME	DEPTH
<p>DST#6 3415-3455',  30-45-60-45, wk blow throughout, rec 70'  mud w/oil spks on top, IFP 36-43#, ISIP  943#, FFP 50-65#, FSIP 812#, BHT 104'.</p> <p>DST#7 3456-3473',  30-45-30-45, strong blow throughout test,  rec 300' MW, IFP 43-94#, ISIP 1030#,  FFP 101-159#, FSIP 979#, BHT 105'.</p>				

Pi

36-7-18W

CONTRACTOR'S WELL LOG

OPERATOR:	F & M OIL CO., INC.
CONTRACTOR:	Union Drilling Co., Inc.
LEASE NAME:	Kansas "B" #1
LOCATION:	SE NW NE Section 36-7S-18W Rooks County, Kansas
COMMENCED:	November 08, 1982
COMPLETED:	November 19, 1982

---

0	3163	Lime & Shale	Set 8-5/8" @ 325' w/350 sxs Lite
3163	3420	Lime	cement 6% gel, 3% CC & 125 sxs
3420	3523	Lime & Shale	common cement 2% gel, 3% CC
3523		RTD	

---

We certify that the above foregoing is a true and correct copy of the log on the Kansas "B" #1, SE NW NE Section 36-7S-18W, Rooks County, Kansas.

Union Drilling Co., Inc.

*R. D. Messinger*  
 \_\_\_\_\_  
 R. D. Messinger

STATE OF KANSAS     )  
                                   ) SS  
 COUNTY OF SEDGWICK )

Subscribed and sworn to before me, a Notary Public in and for the aforesaid County and State as of this 7th day of December, 1982.

My appointment expires:  
 \_\_\_\_\_  
 12-24-84

*Shirley A. Gallegos*  
 \_\_\_\_\_  
 Shirley A. Gallegos-Notary Public

