

KANSAS GEOLOGICAL SOCIETY
KANSAS WELL LOG BUREAU - KANSAS WELL SAMPLE BUREAU
KANSAS GEOLOGICAL SOCIETY BUILDING
505 EAST MURDOCK - WICHITA, KANSAS

COMPANY J. MARK RICHARDSON

SEC. 36 T. 7 N. 18W

FARM Maddy

NO. 1

LOC. NW NW SW

TOTAL DEPTH 3383'

COMM. 2-15-68

COMP. 2-22-68


SHOT OR TREATED

CONTRACTOR Gabbert-Jones Inc.

ISSUED 6-15-68

COUNTY Rooks

KANSAS



CASING

20

10

15

5

12

4

18

5

5/8" 213' cem w/ 140 sx

ELEVATION 1890' KB

PRODUCTION P 17 BOPD PLS 65%

Arb 3342-50 & 3365-80

4 1/2" 3365' cem w/ 100 sx

FIGURES INDICATE BOTTOM OF FORMATIONS

0	60	ROCK
60	115	SHALE AND SHELL
115	125	SAND
125	213	SHALE
213	500	SHALE
500	750	SHALE, SAND AND PYRITE
750	1010	SAND
1010	1020	SHALE
1020	1284	SHALE AND SHELLS
1284	1318	ANHYDRITE
1318	1350	SHALE
1350	1550	SHALE AND SHELLS
1550	1725	LIME AND SHALE
1725	2340	LIME
2340	3013	LIME AND SHALE
3013	3378	LIME
3378	TD	
3383	DDTD	

RAN 11 JOINTS 8-5/8" CASING, SET @ 213' w/140 BAGS CEMENT.

TOPS: LOG

Topeka	2812
Heebner	3021
Toronto	3045
Lansing	3064
Marmaton	3318
Marmaton Zone	3332
Arbuckle	3340
Ltd	3378
RTD	3378
DDTD	3383

RAN 110 JOINTS OF 4 1/2" CASING, SET @ 3365' w/100 BAGS CEMENT.

I, E. E. HALL, CERTIFY THIS IS A CORRECT COPY OF THE DRILLERS' LOG FOR THE WELL DRILLED IN THE NW NW SW SECTION 36-7S-18W, ROOKS COUNTY, KANSAS, TO THE BEST OF MY KNOWLEDGE AND BELIEF.

E. E. Hall

E. E. HALL

STATE OF KANSAS)

COUNTY OF SEDGWICK)

SS

BEFORE ME, THE UNDERSIGNED, A NOTARY PUBLIC WITHIN AND FOR SAID COUNTY AND STATE, ON THIS 26TH DAY OF FEBRUARY, 1968, PERSONALLY APPEARED E. E. HALL, TO ME PERSONALLY KNOWN TO BE THE IDENTICAL PERSON WHO EXECUTED THE WITHIN AND FOREGOING INSTRUMENT AND ACKNOWLEDGED TO ME THAT HE EXECUTED THE SAME AS HIS FREE AND VOLUNTARY ACT AND DEED FOR THE USES AND PURPOSES THEREIN SET FORTH.

IN WITNESS WHEREOF, I HAVE HEREUNTO SET MY HAND AND OFFICIAL SEAL THE DAY AND YEAR LAST ABOVE WRITTEN.