

KANSAS

WELL COMPLETION REPORT AND DRILLER'S LOG

State Geological Survey WICHITA BRANCH

21


S. 36 T. 7-S R. 18 W

Loc. NW/4 NW/4

API No. 15 - Roofs County - 163-21-324 Number

County Roofs

640 Acres N



Locate well correctly

Elev.: Gr. 1903

DF 1905 KB 1908

Operator Rim oil Co

Address 512 S. Wyoming Plainville Mo 67663

Well No. 1 Lease Name Maddy

Footage Location 330 feet from (N) line 430 feet from (W) line

Principal Contractor Lambanco Drilling Inc. Geologist Kenneth Velige

Spud Date 7-13-81 Date Completed 7-18-81 Total Depth 3374 P.B.T.D.

Directional Deviation Oil and/or Gas Purchaser

CASING RECORD

Report of all strings set— surface, intermediate, production, etc.

Purpose of string	Size hole drilled	Size casing set (in O.D.)	Weight lbs./ft.	Setting depth	Type cement	Sacks	Type and percent additives
Surface	12 1/4	8 5/8	20	208	Common	125	2% gel 3% Cc
Long String	7 7/8	5 1/2	15	3374	60/40 Poz	135	8% Salt 2% gel

LINER RECORD

PERFORATION RECORD

Top, ft.	Bottom, ft.	Sacks cement	Shots per ft.	Size & type	Depth interval
			2	3/8 jet	321-25 3180-84
TUBING RECORD				3/8 jet	3339-43
Size	Setting depth	Packer set at			

ACID, FRACTURE, SHOT, CEMENT SQUEEZE RECORD

Amount and kind of material used	Depth interval treated
KC 3221-25 & 3180-84 1500 gal Reg 15% acid	
Marmaton 3339-43 250 gal Reg 16% acid	

INITIAL PRODUCTION

Date of first production Sept 1-81 Producing method (flowing, pumping, gas lift, etc.) pumping

RATE OF PRODUCTION PER 24 HOURS: Oil 8 bbls. Gas none MCF Water 100 bbls. Gas-oil ratio

Disposition of gas (vented, used on lease or sold) Producing interval(s) RC-3221-25 CFPB 3180-84 Marmaton 3339-43

INSTRUCTIONS: As provided in KCC Rule 82-2-125, within 90 days after completion of a well, one completed copy of this Drillers Log shall be transmitted to the State Geological Survey of Kansas, 4150 Monroe Street, Wichita, Kansas 67209. Copies of this form are available from the Conservation Division, State Corporation Commission, 245 No. Water, Wichita, Kansas 67202. Phone AC 316-522-2206. If confidential custody is desired, please note Rule 82-2-125. Drillers Logs will be on open file in the Oil and Gas Division, State Geological Survey of Kansas, Lawrence, Kansas 66044.

Operator

DESIGNATE TYPE OF COMP.: OIL, GAS, DRY HOLE, SWDW, ETC.:

Well No.

Lease Name

S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_ E \_\_\_\_\_  
W

**WELL LOG**

Show all important zones of porosity and contents thereof; cored intervals, and all drill-stem tests, including depth interval tested, cushion used, time tool open, flowing and shut-in pressures, and recoveries.

SHOW GEOLOGICAL MARKERS, LOGS RUN, OR OTHER DESCRIPTIVE INFORMATION.

FORMATION DESCRIPTION, CONTENTS, ETC.	TOP	BOTTOM	NAME	DEPTH

USE ADDITIONAL SHEETS, IF NECESSARY, TO COMPLETE WELL RECORD.

Date Received

Signature

Title

Date