

2-7-19W

State Geological Survey  
WICHITA BRANCH  
CONTRACTORS WELL LOG



OPERATOR:	Baird Oil Company
CONTRACTOR:	Abercrombie Drilling, Inc.
WELL NAME:	GRIEBEL #1
LOCATION:	C NW NW, Sec. 2-7S-19W
	Rooks County, Knasas
SPUD DATE:	8/13/81
COMPLETION DATE:	8/23/81

0	165	Top Soil & Sand
165	696	Sand & Shale
696	1482	Shale
1482	1516	Anhydrite
1516	2760	Shale
2760	3180	Lime & Shale
3180	3224	Lime
3224	3358	Lime & Shale
3358	3504	Lime
	3504	Rotary Total Depth

Spud hole @ 1:00 p.m., 8/13/81. Cut 218' of a 12 1/4" hole. Ran 5 jts. new 8 5/8" 20# casing set @ 217.50' and cemented with 150 sx. Class A 2% gel, 3% c.c. Cement did circulate. Plug was down @ 5:30 p.m., 8/13/81.

3504' TD. Ran 89 jts. of 4 1/2" 9 1/2# casing set @ 3497'. Ran 500 gallons Mud Flush, 35 sx. 50-50 posmix, 2% gel, 12 1/2# Gilsinite per sx. Followed with 200 sx. Common 18% Salt, .75% CFR-2. Job complete @ 7:30 p.m., 8/23/81.

SAMPLE TOPS:

Anhydrite	1492'
B/Anhydrite	1516'

STATE OF KANSAS     )  
                                   ) SS  
 COUNTY OF SEDGWICK )

Jack L. Partridge, Vice President of Abercrombie Drilling, Inc. does hereby state that the above and foregoing is a true and correct copy of the log of the GRIEBEL #1, C NW NW, Sec. 2-7S-19W, Rooks County, Kansas.

ABERCROMBIE DRILLING, INC.