


WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY
 508 East Murdock, Wichita, Kansas

Company- BENNETT & ROBERTS OIL OPERATIONS
 Farm- Riffe "A" No. 3

SEC. 4 T. 7 R. 19W
 C N/2 SW SW

Total Depth. 3512'
 Comm. 10-16-58 Comp. 10-24-58
 Shot or Treated.
 Contractor. Bennett & Roberts Drlg. Co.
 Issued. 12-6-58

County Rocks KANSAS



Elevation. 2015 DF

Production. 25 BOPD

CASING:

8 5/8" 182' w/125 sx. cem.
 5 1/2" 3438' w/125 sx. cem.

Figures Indicate Bottom of Formations.

surface soil & clay	50
sand	140
gray shale	175
shale	185
shale and shells	210
shale	400
shale and shells	680
sand	900
sand	910
shale and sand	1000
shale and sand	1034
shale	1050
Dakota Sand	1265
shale, shells & red bed	1550
anhydrite	1573
shale and shells	2015
shale and lime	3100
lime	3512 RTD
Total Depth	

FORMATION TOPS

Cimmerron Anhydrite	1550 (Driller)
Topeka Lime	2967
Heebner shale	3167
Toronto Lime	3192
Lansing Kansas City	3211
Basal Kansas City	3414
Weathered Arbuckle	3474

DST #1 Prosser Tester, dual packers, 13' anchor. 3217-30 Tool open 1 hr., strong to good blow 60 mins., recovered 1020' clean oil, 1230' gas in pipe, 9' muddy oil. BHP in 10 mins. 1015 p.s.i., IFP 130 p.s.i., FFP 385 p.s.i.

DST #2 Prosser Testers, dual packers, 20' anchor. 3253-73 Tool open 1 hr., good blow 60 mins., recovered 720' gas in pipe, 100' clean oil, 10' froggy oil, 10' oil cut mud. BHP in 20 mins. 400 p.s.i.

DST #3 Prosser Testers, dual packers, 18' anchor. 3289-3307 Tool open 1 hr., fair blow 60 mins., recovered 180' muddy water slightly gassy, BHP in 20 mins., 910 p.s.i., IFP 0 p.s.i. FFP 185 p.s.i.

DST #4 Prosser Testers, dual packers, 15' anchor. 3373-88 Tool open 1 hr., weak blow 8 mins., recovered 2' free oil 10' oil and water cut mud. BHP in 20 mins., 135 p.s.i.

No electric log run.