

WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY

500 East Murdock,


Wichita, Kansas

Company- BENNETT & ROBERTS OIL
 Farm- Riffe "A" No. 5

SEC. 4 T. 7 R. 19W
 C S/2 SW SW

Total Depth. 3460'
 Comm. 4-7-59 Comp. 4-15-59
 Shot or Treated.
 Contractor. Bennett & Roberts Drlg.
 Issued 8-15-59

County Rooks
 KANSAS



CASING:

8 5/8" 180' cem w/125 sx.
 5 1/2" 3449' cem w/125 sx.

Elevation. 1988' DF

Production. 25 BOPD

Figures Indicate Bottom of Formations.

shale & sand	20
shale	70
shale & shells	180
shale	460
shale & sand	570
shale	625
sand	655
shale & sand	775
shale	840
sand	905
shale & sand	995
sand	1210
sand & shale	1240
red bed	1510
Anhydrite	1545
shale & shells	1930
lime & shale	3005
lime	3145
lime & shale	3210
lime	3460 RTD
Total Depth	

TOPS:

Cimmerron Anhydrite	1545
Heebner Shale	3146
Toronto Lime	3174
Lansing-Kansas City	3189
Arbuckle	3448

DST #1 single packer, 14' anchor,
 3196-3210', op 60 mins., weak blow for
 30 mins., intermittent 30 mins. Rec. 40'
 formation water. BHP 565#/20 mins.
 IFP 0#, FFP 0#.

DST #2 single packer, 39' anchor
 3217-3256', op 60 mins., fair blow 60
 mins., rec. 115' muddy oil, 305' gas on
 top of fluid. BHP 530#/20 mins., IFP 105#,
 FFP 190#.

DST #3 single packer, 29' anchor.
 3266-3295', op 60 mins., weak blow
 intermittent, 60 mins., rec. 35' heavy
 mud, slightly gassy w/few specks of oil.
 BHP 905#/20 mins., IFP 0#, FFP 0#.

DST #4 dual packers, 10' anchor.
 3450-3460', op 45 mins., weak blow 2
 mins., rec. 5' oil cut mud, 1 pt. free
 oil. BHP 0#/20 mins. IFP 0#. FFP 0#.