

WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY  
508 East Murdock, Wichita, Kansas


15-163-01310

Company- BENNETT & ROBERTS OIL  
Farm- Dryden No. 1

SEC. 5 T. 7 R. 19W  
C E/2 SE SE

Total Depth. 3484'  
Comm. 6-8-59 Comp. 6-17-59  
Shot or Treated.  
Contractor. Bennett & Roberts Drlg.  
Issued. 10-17-59

County Rooks  
KANSAS



Elevation. 2011' DF

Production. 25 BOPD

CASING:

8 5/8" 189' cem w/130 sx.  
5 1/2" 3480' cem w/125 sx.

Figures Indicate Bottom of Formations.

clay & shale	70
sand	80
shale	570
sand	630
shale	660
sand	730
shale	850
sand	925
shale & shells	1050
sand & shale	1265
red bed	1525
Anhydrite	1555
shale & shells	1940
lime & shale	3115
lime	3403
lime & shale	3484 RTD
Total Depth	

TOPS:

Topeka	2969
Heebner	3165
Toronto	3194
Lansing	3205
Base Kansas City	3413
Arbuckle	3479

DST #1 3202-3228', op 1 hr, good blow,  
diminishing some at last. Rec. 120'  
slightly oil-cut mud and water. 540'  
slightly oil-cut water. IFP 245#,  
FFP 480#, BHP 705#/20 mins.

DST #2 3236-68', op 1 hr w/a good blow,  
rec. 1272' gas, 420' clean oil, 120'  
muddy oil. IFP 205#, FFP 365#, BHP 515#/  
20 mins.

DST #3 3286-3305', op 1 hr w/a weak to  
intermittent blow, rec. 37' slightly oil  
cut mud. IFP 80#, FFP 90#, BHP 925#/20 mins.

DST #4 3355-96', op 1 hr w/a weak inter-  
mittent blow, rec. 5' of clean oil and 15'  
of oil-cut mud. IFP 120#, FFP 130#,  
BHP 305#/20 mins.

DST #5 3380-3384', op 1 hr. w/a very weak  
intermittent blow, rec. 8' of clean oil,  
7' of oil cut mud. IFP & FFP 55#,  
BHP 1050#/20 mins.