


WELL LOG BUREAU--KANSAS GEOLOGICAL SOCIETY
508 East Murdock, Wichita, Kansas

Company- BENNETT & ROBERTS OIL
Farm- Dryden No. 2

SEC. 5 T. 7 R. 19W
C W/2 SE SE

Total Depth. 3493'
Comm. 9-1-59 Comp. 9-9-59
Shot or Treated.
Contractor.
Issued. 12-26-59

County Rooks
KANSAS



Elevation. 2007' DF

Production. 60 BOPD

CASING:

8 5/8" 189' cem w/100 sx.
5 1/2" 3479½' cem w/125 sx.

Figures Indicate Bottom of Formations.

surface soil & 'clay	40
shale	285
sand	690
sand & shale	960
sand	990
shale	1040
sand	1250
red bed & shale	1530
Anhydrite	1566
shale & shells	2130
lime & 'shale	3050
lime	3493 RTD
Total Depth	

TOPS:

Anhydrite	1530
Topeka	2964
Heebner	3163
Toronto	3187
Lansing	3204
Base Kansas City	3409
Arbuckle	3476

DST #1 3134-3169', op 1 hr, with fair blow, rec. 75' of slightly medium oil cut mud. Shut in 20". BHP 790#, no flow pressures.

DST #2 3195-3217', op 1 hr, with a fair blow, rec. 110' of very slightly oil-cut watery mud. No pressures were obtained due to failure of the recording instrument.

DST #3 3237-3267', op 1 hr., w/a weak intermittent blow for only 10 min., shut in 20 min., rec. 12' slightly oil-cut mud. No pressures.

DST #4 3267-3317', op 1 hr w/a good blow, rec. 260' of watery mud. BHP 990# 20 min., IFP 90#, FFP 255#.

DST #5 3358-3387', op 1 hr. w/a fair blow rec. 50' gas, 20' clean oil, 50' heavily oil-cut mud. The tool was shut in 20 min. but no pressures were recorded.

DST #6 3480-90', op 1 hr, w/a weak blow, rec. 5' of clean oil, 50' of muddy oil. BHP 1010#/20 mins., There were no flow pressures.