

5-7-19W


WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY
508 East Murdock, Wichita, Kansas

Company. SIERRA PETROLEUM CO. ET AL
Farm- Long No. 1

SEC. 5 T. 7 R. 19W
SE SE SW

Total Depth. 3600'
Comm. 10-26-60 Comp. 11-5-60
Shot or Treated.
Contractor.
Issued. 3-11-61

County Rooks
KANSAS



CASING:
8 5/8" 182' cem w/125 sz.
5 1/2" 3525' cem w/175 sz.

Elevation. 1983' DF

Production. 10 BOPD

Figures Indicate Bottom of Formations.

surface soil & shale	40
shale	385
sand & shale	430
shale & shells	855
sandy shale	930
sand & shale	1010
sand	1230
red bed & shale	1512
Anhydrite	1547
shale, shells (Few Lime Strks)	1770
shale & shells	2040
shale & lime	2973
lime	3367
lime & shale	3384
lime & Conglomerate	3441
Conglomerate	3444
Arbuckle	3546
Reagan Sand	3556
Granite Wash	3600
Total Depth	

TOPS:	
Anhydrite	1512
Topeka	2947
Heebner	3146
Toronto	3170
Lansing-Kansas City	3187
Arbuckle	3444
Reagan Sand (scout)	3535
Granite Wash (scout)	3556