

WELL LOG BUREAU — KANSAS GEOLOGICAL SOCIETY
412 Union National Bk. Bldg., Wichita, Kansas

Company - SAM PACK
Farm - Griebel


No. 1

SEC. 8 T. 7 R. 19W
NE NE NW

Total Depth. 3456
Comm. 11-29-48 Comp. 12-11-48
Shot or Treated. acidized with 500 gal re-acidized with 1500 gal
Contractor. Braden & Greene Drilling Co.
Issued. 6-18-49

County. Rooks

KANSAS



CASING:
8 5/8" 216' 17"
5 1/2" 3454' cem w/100sx

Elevation. 1984

Production. 25 BOPD

Figures Indicate Bottom of Formations.

Shale	30
sand	40
sand, shale	100
shale, shells	210
shale	590
sand	605
shale	830
sand, shale	980
sand	1220
sand, shale	1230
iron, sand	1280
shale, sand	1335
red rock, shale	1515
a nhydrite	1555
shale, red rock	1570
shale, sdy, shell	1930
lime, shale	2815
limo, shale	2875
shale	2965
shale, limo	3060
limo	3105
limo, shale	3230
limo	3265
limo, shale	3380
shale, limo	3455
limo	3456
Total Depth	

TOPS:
Casing 3187
Arbuckle 3438

Set 5 1/2" casing at 3446'
w/100 sx com. Drilled plug
Swabbed to bottom
Filled up 100' muddy oil in
9 hr.
Acidized w/500 gal. Pressure
went from 900# to 1050# and
broke to 350#
Swabbed into tank 22 bbl oil
in 9 hr
Re-acidized w/1500 gal
Tested 5 BOPH, no wtr, 27
gravity oil
Temporary allowable 25 BOPD
effective 12-31-48
Pmpd. 7 1/2 bbl oil 52 1/2 bbl wtr
in 24 hr 5 bbl oil, 36 bbl
wtr in 24 hr 5 bbl oi, 35 bbl wtr
in 24 hr 20 bbl oil, 40 bbl wtr
in 24 hr.
Producing area 3446-3456