


WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY
508 East Murdock, Wichita, Kansas

Company. BENNETT & ROBERTS OIL
Farm- Desmarteau No. 1

SEC. 9 T. 7 R. 19W
NE NW NE

Total Depth. 3507'
Comm. 11-1-58 Comp. 11-11-58
Shot or Treated.
Contractor. Bennett & Roberts
Issued. 12-20-58

County Rooks
KANSAS



CASING:

8 5/8" 211' cem w/125 sx.

Elevation. 2004' DF

Production. Dry

Figures Indicate Bottom of Formations.

clay	50
sand	70
shale & sand	130
gray shale	195
blue shale	595
sand	905
hard sand	935
shale & shells	1030
sand	1245
shale & red bed	1300
shale, stks, hard	
sand, red bed	1425
shale	1560
Anhydrite	1590
shale & red bed	1825
shale & shells	1950
lime & shale	3202
lime	3472
Conglomerate	3489
lime	3507 RTD
Total Depth	

TOPS: RB MEAS.

Cimmerron Anhydrite	1560 (Driller)
Topeka Lime	2960
Heebner Shale	3161
Toronto Lime	3190
Lansing-Kansas City	3205
Base Kansas City	3412
Conglomerate Shale	3472
Weathered Arbuckle	3486

No electric log run.

DRILL STEM TESTS:

#1 Prosser Testers INC. single packer, 9' anchor
3216-25 op 1 hr, weak blow 35 mins, rec.
1' free oil, 5' oil cut mud, 24' oil
specked mud w/trace of wtr. BHP 415#/20 mins.

#2 Prosser Testers Inc. single packer, 34' anchor.
3251-85, op 1 hr., weak blow 5 mins., rec. 15'
oil cut mud, BHP 605#/20 mins.

#3 Prosser Testers Inc. single packer, 21' anchor.
3341-62, op 1 hr, weak blow 6 mins., rec. 1' muddy
oil & 8' oil cut mud. BHP 390#/20 mins.

#4 Prosser Testers, Inc. single packer, 16' anchor
3370-86, op 1 hr, weak blow 6 mins., rec. 8' oil
cut mud w/scum of free oil. BHP 0#/20 mins.

#5 Prosser Testers, Inc. single packer, 7' anchor.
3489-96, op 45 min, weak blow 3 mins., rec. 5' oil
cut mud, scum of free oil. BHP 505#/20 mins.

#6 Prosser Testers, Inc. dual packers, 7' anchor.
3495-3502, op 45 mins., weak blow 4 mins., rec. 6'
oil cut mud & 1 pint free oil. BHP 290#/20 mins.