


WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY
 508 East Murdock, Wichita, Kansas

Company- **BENNETT & ROBERTS OIL**
 Farm- **Desmarteau** No. **3**

SEC. **9** T. **7** R. **19W**
 NW NW NW

Total Depth. **3477'**
 Comm. **6-19-59** Comp. **6-27-59**
 Shot or Treated.
 Contractor.
 Issued. **10-17-59**

County **Rooks**
KANSAS



Elevation. **2004'** RB

Production. **25 BOPD**

CASING:

8 5/8" 187' cem w/130 sx.
5 1/2" 3472' cem w/125 sx.

Figures indicate Bottom of Formations.

surface soil & clay	40
clay	90
sand	100
shale	590
sand	620
shale	650
sand	680
shale	790
sand	910
shale	1020
sand	1240
shale	1260
red bed	1525
Anhydrite	1560
shale & shells	1740
shale & lime	3120
lime	3477 RTD
Total Depth	

TOPS:

Topeka	2949
Heebner	3154
Toronto	3180
Lansing	3195
Base Kansas City	3433
Conglomerate	3459
Arbuckle	3470

DST #1 3188-3216', op 1 hr., w/a good blow thruout, rec. 140' gas, 30' clean oil, 74' of heavily oil-cut mud. No flow pressures. BHP 465#/20 mins.

DST #2 3234-3261', op 1 hr, w/a good blow thruout, rec. 670' of gas, 580' of clean oil, and 70' of muddy oil. IFP 105#, FFP 255#, BHP 350#/20 mins.

DST #3 3272-3296', op 1 hr., w/a weak but steady blow thruout, rec. 105' of mud w/a few streaks of oil. No flow pressures. BHP 815#/20 mins.

DST #4 3351-77', op 1 hr., w/a weak, but steady blow thruout the test, rec. 17' of clean oil, and 20' of muddy oil. There were no flow pressures; BHP 525#/20 mins.

DST #5 3472-77', op 1 hr., w/a weak intermittent blow for only 8 mins., rec. 1' of clean oil, and 7' of muddy oil.