

WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY

508 East Murdock,

Wichita, Kansas

Company- BENNETT & ROBERTS OIL  
Farm- Desmarteau No. 4

SEC. 9 T. 7 R. 19W  
NW SW NW

Total Depth. 3480'

Comm. 7-13-59

Comp. 7-21-59


Shot or Treated.

Contractor.

Issued. 10-17-59

County Rooks

KANSAS



Elevation. 1986' RB

Production. Dry

CASING:

8 5/8" 188' cem w/130 sx.

Figures indicate Bottom of Formations.

surface soil	35
sand	70
shale	188
sand	250
shale	360
shale	425
sand	560
shale	770
sand	810
shale	840
sand	900
shale & shells	1010
sand	1220
shale & red bed	1520
Anhydrite	1550
shale & shells	2175
shale & lime	2555
shale & lime streaks	2700
shale & lime	2995
shale & lime streaks	3107
shale & lime	3185
lime	3480 RTD
Total Depth	

TOPS:

Topeka	2939
Heebner	3141
Toronto	3164
Lansing	3181
Base Kansas City	3422
Arbuckle	3475

DST #1 3168-3205', op 1 hr., w/a very weak, intermittent blow; rec. 28' of mud w/a few specks of oil. IFP 110#, FFP 140#, BHP 925#/20 mins.

DST #2 3220-3252', op 1 hr w/very weak blow 10 mins; rec. 5' mud w/slight show of oil. IFP & FFP both 105#, BHP 535#/30 mins.

DST #3 3252-96', op 1 hr w/a weak blow for only 8 mins; rec. 15' of mud w/very few specks of oil. IFP & FFP both 130#, BHP 1060#/30 mins.

DST #4 3324-3360', op 1 hr, w/a weak blow for only 5 mins.; rec. 4' oil-cut mud w/about a cup of free oil in the top of the tool. BHP 0#/30 mins.

DST #5 3435-80', op 1 hr., w/a weak intermittent blow for 17 mins; rec. 3' oil, and 17' of slightly oil-cut mud. IFP & FFP both 145#, BHP 690#/30 mins.