

WELL LOG BUREAU--KANSAS GEOLOGICAL SOCIETY
508 East Murdock, Wichita, Kansas


15-103-01318

Company. MAGNOLIA PETROLEUM
Farm. Bessie Burton No. 2

SEC. 14 T. 7 R. 19W
SE NW SW

Total Depth. 3415 F.B. 3338
Comm. 5-17-52 Comp. 6-5-52
Shots Treated. Acidized
Contractor. Barnett Drlg.
Issued. 8-2-52

County Rooks
KANSAS



Elevation. 1924 D.F.

Production. 116 BO & 16 BW

CASING:

8 5/8" 197'
5 1/2" 3403'

Figures indicate Bottom of Formations.

sand & shale	40
shells & shale	197
shale & shells	570
sdv shale & shells	900
sand	1110
sdv shale	1380
shells & shale	1400
anhyd.	1433
shale & shale	1920
lime & shale	3095
lime	3365
lime & congl.	3415
Total Depth	

Tops:	
Heebner	3071
Mansing	3104
Arbuckle	3402

R.F.D. 3407, drilled out cem. to 3408, bailed 5 hrs., dry, no show
D.D. to 3415 SSO 3413-15, tested 1 qt. oil & 15 GWP, 3 hrs.
Az. w/1000 gals. 106 BLO, ret. load oil & swb. 4 bswph, no oil. Set plug 3338 tested dry, perf. 3320-26 w/24 sh., no show, az. w/1000 gals., BLO 102. Ret. load oil, tested 2 hrs., swb 1 1/2 BO & 1/4 BAWPH
Set plug 3314, perf. 3294-3306 w/48 sh., az. 2000 gals., swb 3 1/4 BOPH, 9 hrs. Drld. plug 3314. Pmp 116 BO & 16 BW in 24 hrs.