

15-103-30180
15-7-19W

WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY
508 East Murdock, Wichita, Kansas

Company- AYLWARD DRILG.
Farm- Holsman

No. 1

SEC. 15

T. 7
SE SW SE

R.19W

Total Depth. 3423

Comm. 8-26-65

Shot or Treated.


Contractor. Aylward Drlg.

Issued. 12-18-65

Comp. 9-3-65

County Rocks

KANSAS



Elevation. 1949' KB

Production. 25 BOPD

CASING:

8 5/8" @ 278' w/175 sx.
5 1/2" @ 3407' w/100 sx.

Figures Indicate Bottom of Formations.

surface clay	40
red clay	150
blue shale	278
shale	555
sand	585
shale	945
sand	1130
shale & lime	1490
shale & shells	1865
shale	2000
lime	2010
sand	2032
shale & lime	3120
lime	3410
Total Depth	

TOPS: Log

Topeka	2891
Heebner	3096
Foronto	3121
Lansing	3135
Arbuckle	3405

DST 3100-50 Opn. 30", Rec. 10' mud. IBHP
545#/20"- FBHP 352#/30", FP 50-58#.

DST 3280-3320 Opn. 1 hr. Rec. 180' vry.
heavy O & GCM, 70' OGM, IBHP 637#/20"-
FBHP 326#/30", FP 83-158#.

GCM