

WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY
508 East Murdock, Wichita, Kansas

15-163-70462


Company- MAGNOLIA PETROLEUM CO.
Farm- C. Holsman "B" No. 1

SEC. 15 T. 7 R. 19W
SE NE SE

Total Depth. 3538 P.B. 3415 K.B.
Comm. 11-6-51 Comp. 12-24-51
Shot or Treated. Acidized
Contractor. Mallonee Drlg. Co.
Issued. 2-2-52

County Rooks

KANSAS



Elevation. 1958 D.F.

Production. P. 72 bbl., no wtr.
24 hrs.

Figures Indicate Bottom of Formations.

CASING:
10 3/4" 195' cem. w/175 sx.
6 5/8" 3466' cem. w/300 sx.

surface soil, clay &	
sand	45
shale	200
shale & shells	550
shale blue	686
red bed	768
sand rock	775
strks sand & shale	930
sand hrd	983
Dakota sand	1180
red bed & sdy lime	1250
red bed	1464
anhyd.	1505
shale & shells	1705
lime brkn & shale	1760
lime brkn & red bed	1840
lime & shale	1925
lime brkn & shale	2025
lime, shale	2070
lime & shale	2165
lime brkn & shale	2200
lime & hrd shale w/	
strks pyrite	2238
shale & lime	2248
shale & pyrite	2283
shale & shells	2400
lime	2430
lime brkn & shale	2488
pyrite, lime & shale	2525
lime brkn	2575
shale	2600
lime	2620
strks lime & shale	2626
lime & shale	2695
lime brkn	2740
lime brkn & shale	2755
lime chalky	2815
lime & shale	2913
lime	3108
lime & shale	3118
lime	3538
Total Depth K.B. P.B. 3415	

Set plug 3235, perf. 3212-20
w/24 sh., acidized. w/4000 gals. wwb
2 BWP w/show oil 20 hrs.
Sq. perfs. 3194-3200 and 3212-20
Perf. 3162-68 w/18 sh. & 3154-59 w/15
sh., no show. az w/4000 gals., test 2
BAWPH 12 hrs.,
Stratalift perfs. 3154-59 and 3162-68
test 1 1/2 BWP, no oil. Sq. perf. 3154-59
and 3162-68.

Tops: K.B.
Lansing 3153
Arb. 3423
Basal sand 3520
Pre-Cambrian 3537

P.B. 3419, per. 3352-57 w/24
sh., acidized w/2000 gals. tested 3
bo & 2 BAW in 4 hrs., reacidized w/4000
gals. test 2 1/2 bo & 1/2 BAWPH, 3 hrs.
Set plug 3346, per. 3329-37 w/24 sh.,
bailed 10 GO & 10 G muddy wtr., 30 m ns.,
acidized w/4000 gals., tested 3 hrs. 6 BOPH
no wtr. Drove plug to 3415 Set plug, perf.
3309-20 w/44 sh., test 5 GO & 20 G muddy wtr.,
az. w/4000 gals., test 7 BOPH, no wtr.
3 hrs. Set plug 3208, perf. 3194-3200 w/
24 sh., az. 2/4000 gals. test 13 hrs. 1/2
BWP, show oil.