

CONFIDENTIAL

State Geological Survey

10/19/81
J. G. P. 1

AFFIDAVIT AND COMPLETION FORM

WICHITA BRANCH

ACO-1

17-2-19W

This form must be filed in triplicate with the Kansas Corporation Commission, 200 Colorado Derby Building, Wichita, Kansas 67202, within five days after the completion of the well, regardless of how the well was completed. Circle one: Oil, gas, dry, SWD, OWWO, injection. Please type. Complete ALL sections. Applications must be filed for dual completion, commingling, salt water disposal and injection. Attach wireline logs (i.e. electrical log, sonic log, gamma ray neutron log, etc.) KCC#-(316) 263-3238.

OPERATOR Petro-Mining Resources, Inc.API NO. 15-163-21,418ADDRESS P.O. Drawer 298COUNTY RooksOberlin, Kansas 67749FIELD Wildcat**CONTACT PERSON James R. BettsLEASE J. GriebelPHONE 913-475-3801 **DEC 28 1981**PURCHASER Clear Creek, Inc.WELL NO. SW1-17ADDRESS 818 Century Plaza Bldg.WELL LOCATION SE/SE/SW/4Wichita, Ks. 67202250 Ft. from South Line and250 Ft. from East Line ofDRILLING CONTRACTOR Circle M Drilling Co.the SE/4 SEC. 17 TWP. 7-S RGE. 19-WADDRESS P.O. Box 128Oberlin, Kansas 67749PLUGGING CONTRACTOR N/A


ADDRESS _____

TOTAL DEPTH 3527' PBDT 3422'SPUD DATE 9-15-81 DATE COMPLETED 10-19-81ELEV: GR 1972DF N/A KB 1978'

DRILLED WITH (CABLE) (ROTARY) (AIR) TOOLS

Report of all strings set — surface, intermediate, production, etc. (New)/(Used) casing.

Purpose of string	Size hole drilled	Size casing set (in O.D.)	Weight lbs/ft.	Setting depth	Type cement	Sacks	Type and percent additives
Surface	12 1/4"	8 5/8"	24#	210'	60/40 pos.	150	2% gel, 3% cc
Production	7 7/8"	5 1/2"	14#	3522'	60/40 pos. 50/50 pos	180	2% gel, 10% salt

WELL
PLAT(Quarter)
or (Full)
Section -
Please
indicate.KCC
KGS ✓

LINER RECORD				PERFORATION RECORD		
Top, ft.	Bottom, ft.	Sacks cement		Shots per ft.	Size & type	Depth interval
	N/A			Tight hole		
TUBING RECORD						
Size	Setting depth	Packer set at				
2 3/8"	3419.95'	(T.A.)				

ACID, FRACTURE, SHOT, CEMENT SQUEEZE RECORD

Amount and kind of material used		Depth interval treated
tight hole	Date: 1 OCT 1982	RECEIVED
	FROM CONFIDENTIAL	STATE CORPORATION COMMISSION

RELEASED

NOV 17 1981

17-7-19w PC

Name of lowest fresh water producing stratum unknown Depth
 Estimated height of cement behind pipe 1900'

WELL LOG

Show all important zones of porosity and contents thereof; cored intervals, and all drill-stem tests, including depth interval tested, cushion used, time tool open, flowing and shut-in pressures, and recoveries.

SHOW GEOLOGICAL MARKERS, LOGS RUN, OR OTHER DESCRIPTIVE INFORMATION.

FORMATION DESCRIPTION, CONTENTS, ETC.	TOP	BOTTOM	NAME	DEPTH
Tight hole info. not available for release until Nov. 1, 1983. See attached log, not available for release until Nov. 1, 1983.				17-7-19w J. Griebel SW1-17

TEST DATE:

PRODUCTION

November 3, 1981

CONSERVATION DIVISION
Wichita Kansas

Date of first production tight hole		Producing method (flowing, pumping, gas lift, etc.) pumping		A.P.I. Gravity 32	
RATE OF PRODUCTION PER 24 HOURS		Oil 10 bbls.	Gas MCF	Water 0 bbls.	Gas-oil ratio CFPB
Disposition of gas (vented, used on lease or sold) N/A				Producing interval(s) not available	

** The person who can be reached by phone regarding any questions concerning this information.

A witnessed initial test by the Commission is required if the well produces more than 25 BOPD or is located in a Basic Order Pool.

State Geological Survey
WICHITA BRANCH

JAN 22 1982

17-7-196

DRILLERS LOG
J. GRIEBEL SW1-17

CASING RECORD:

8 5/8" set at 208

TOTAL DEPTH: 3527'

DESCRIPTION:

SESE/SW

Sec. 17, Twp. 7, Rg. 19. ~~W~~

OPERATOR: Petro-Mining Resources, Inc.

CONTRACTOR: Circle M Drilling Co.

COMMENCED: September 15, 1981


COMPLETED: October 19, 1981

FORMATION	FROM	TO
Shale	0	208
Sand & Shale	208	1484
Anhydrite	1484	1520
Shale	1520	2380
Lime & Shale	2380	2924
Lime	2924	3382
Shale & lime	3382	3412
Dolomite-sand- granite wash	3412	3527


Run 5½" Casing


I certify that the above is a true and correct copy of the log to the best of my knowledge.

Circle M Drilling


Larry D. Taylor

Subscribed and sworn to before me this 5 day of January, 1982.




Notary Public

My commission expires May 18, 1985.