

I am the Affiant, and I am familiar with the contents of the foregoing Affidavit. The statements and allegations contained therein are true and correct.

SIDE TWO
OPERATOR

Energy Exploration Co. LEASE STICE

ACO-1 WELL HISTORY

SEC. 19 TWP. 7S RGE. 19W

WELL NO. 1

FILL IN WELL INFORMATION AS REQUIRED:

Show all important zones of porosity and contents thereof; cored intervals, and all drill-stem tests, including depth interval tested, cushion used, time tool open, flowing and shut-in pressures, and recoveries.

SHOW GEOLOGICAL MARKERS, LOGS RUN, OR OTHER DESCRIPTIVE INFORMATION.

FORMATION DESCRIPTION, CONTENTS, ETC.	TOP	BOTTOM	NAME	DEPTH
Top Soil, Sand & Shale	0	209	SAMPLE TOPS:	
Shale & Sand	209	1506		
Anhydrite	1506	1540	Anhydrite B/Anhyd.	1506'
Shale	1540	1965		1540'
Lime & Shale	1965	2285	FORMATION TOPS	
Shale	2285	2713		
Shale & Lime	2713	3205	Sample Log:	
Lime	3205	3480		
Rotary Total Depth	3480			
DST #1 3118-55, 35-57-60-60, Rec. 30' wtry mud, 120' mdy wtr., ISIP 1099, FSIP 1033, IFP 38-48, FFP 71-92			Anhy.	1506 (+408)
			B/Anhy.	1540 (+454)
			Topeka	2948 (-954)
			Heebner	3150 (-1156)
			Toronto	3177 (-1153)
			Lansing	3190 (-1196)
			Base Ks. City	3400 (-1406)
			Arbuckle	3443 (-1449)
DST #2 3332-60, 30-57-30-60, Rec. 30' OCM 10% oil, 1' oil on top of tool ISIP 409, FSIP 443, IFP 30-47, FFP 30-68				
DST #3 3360-3400, 30-60-30-60, Rec. 10' mud w/sli trace of oil on top, ISIP 422, FSIP 250, IFP 57-57, FFP 65-65				
DST #4 3433-55, 30-60-60-60, Rec. 15' oil, 31 gravity, 60' wtry. MCO 70% oil, 20% wtr., 10% mud, 60' OC wtry. mud, 55% mud, 35% wtr. 10% oil, ISIP 261, FSIP 246, IFP 57-69, FFP 91-108				

Report of all strings set—surface, intermediate, production, etc. CASING RECORD (New) or (Used)

Purpose of string	Size hole drilled	Size casing set (in O.D.)	Weight lbs/ft.	Setting depth	Type cement	Sacks	Type and percent additives
Surface	12 1/4"	8 5/8"	20#	207'	Common	180	2% gel, 3% c.c.

LINER RECORD

PERFORATION RECORD

Top, ft.	Bottom, ft.	Sacks cement	Shots per ft.	Size & type	Depth interval
	N/A				
TUBING RECORD				N/A	