

15-163-02978

WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY
508 East Murdock, Wichita, Kansas


Company- **MAGNOLIA PETROLEUM COMPANY**
 Farm- **Clarence Holsman** No. **2**

SEC. **15** T. **7** R. **19W**
 NW SE SE

Total Depth. **3408 PB 3383**
 Comm. **9-17-52** Comp. **10-19-52**
 Shot or Treated. **Acidized**
 Contractor. **Mallonee Drilling Co.**
 Issued. **11-29-52**

County **Rooks**

KANSAS



Elevation. **1947 D.F.**

1949 KB
 Production. **P. 195 BO & no wtr**

CASING:

5/8" 195' cem w/150 sx
1/2" 3407' cem w/200 sx

Figures Indicate Bottom of Formations.

surface soil	140
shale blue	195
shale, shells	545
shale	800
shale, lime shells	850
shale	915
sand	1120
sand, shale	1250
shale	1425
lime, shale	1665
shale, lime shells	1800
shale	1835
shale, shells	1935
lime, shale	2380
lime brkn, shale	2480
shale, shells	2555
shale, lime	2705
lime brkn, shale	2830
shale, shells	2890
lime, shale	3145
lime	3408
Total Depth	
PB 3383	

Tops:

Heebner	3099
Lansing	3138
Arbuckle	3406

PB 3383, perf. 3334-40 w/24
sh., acidized w/1000 gals.
swb 3 boph, nw. Set plug
3325, perf. 3310-18 w/24 sh.,
acidized w/1000 gals., swb 8
boph, nw, 5 hrs. Drove plug
to 3383.

Set plug 3305, perf. 3290-98
w/24 sh., acidized w/1000 gals.
Swab 10 BOPH, NW, 5 hrs.
Drove plug to bottom.