

15-163-70461

KANSAS WELL LOG BUREAU --- KANSAS GEOLOGICAL SOCIETY
508 EAST MURDOCK - WICHITA, KANSAS

COMPANY MAGNOLIA PETROLEUM CO.

SEC. 15 T. 7 R. 19W

FARM Clarence Holsman NO. 1

LOC. SE SE SE

TOTAL DEPTH 3421 K. B.

COMM. 1-28-51


COMP. 2-17-51

SHOT OR TREATED Acidized

CONTRACTOR Mallonee Drilling Co.

ISSUED 3-24-51

COUNTY Rooks



CASING

8 5/8" 194' cem. w/125 sx

5 1/2" 3408' cem. w/150 sx

ELEVATION 1942 DF

PRODUCTION 28 BO & 212 EWPD

FIGURES INDICATE BOTTOM OF FORMATIONS

clay & shale	195
shale, red bed & sand	895
shale, sand & red rock	1380
red bed, shale & shells	1457
shale & shells	1660
shells, shale, lime strks	
& sandy lime	1875
sandy lime	1955
sandy lime & shale	2080
lime & shale	2240
sandy lime & shale	2395
shale & lime	2490
lime	2535
shale & shells	2885
shale & lime strks	2975
shale & lime	3000
lime & shale	3072
lime	3153
lime & shale	3195
lime	3370
lime & shale	3396
lime	3421 K.B.
Total Depth	

Tops: K.B.

Lansing 3125

Arbuckle 3398

DST: 3053-72, open 1 hr, blow
for 11 min., rec. 40' slightly
oil cut mud.

DST 3274-3309, open 1 hr, rec.
30' mud with light show oil.

DST, 3391-3404, open 45 min.,
ver. weak blow 5 min., rec.

7' drilling mud.

Cored 3404-09, rec. 5', bottom

3" good saturation

Acidized w/3500 gals. acid.