

22-7-19W
15-163-21401

State Geological Survey
WICHITA BRANCH

WELL LOG

OPERATOR: Thomason Oil Company

WELL NAME: Holsman #2 LOCATION: NE SW NE 22-7s-19W

COUNTY: Rooks STATE: Kansas

WELL COMMENCED: September 10, 1981 WELL COMPLETED: September 15, 1981

ELEVATION: 1920' K.B. TOTAL DEPTH: 3440'

PRODUCTION: Oil RIG NO: #4

CASING - 8 5/8": 8 Jts new 20# set @ 323.48' cemented with 180 sxs common 3%cc 2%gel

4 1/2" ~~5XXXXX~~: 82 Jts new 10.5# tallied @ 3429.64' set @ 3438' cemented with 125 sxs common
5 sxs 10% salt P.D.@ 1:30 A.M. 9-15-81

P.D.@ 1:45 A.M. 9-11-81

ALL MEASUREMENTS TAKEN FROM THE TOP OF ROTARY BUSHING:

FROM	TO	FORMATION	DEVIATION FROM VERTICAL	REMARKS:
0'	290'	sand and shale		
290'	327'	sand and shales	327' - 3/4 degree	
327'	355'	sand and shales		
355'	1414'	sand and shale		
1414'	1416'	anhydrite		
1416'	1454'	anhydrite		
1454'	1512'	shale and sand	1512' - 1 1/2 degree	
1512'	1811'	shale		
1811'	2071'	shales		
2071'	2235'	shales	2235' - 1/4 degree	
2235'	2470'	shale and lime		
2470'	2726'	shale and lime		
2726'	2942'	shale and lime		
2942'	3142'	shale and lime		
3142'	3300'	shale and lime		
3300'	3426'	shale and lime		
3426'	3440'	shale and lime	3440' - 1 degree	
3440'	R.T.D.			

RECEIVED
STATE GEOLOGICAL SURVEY

COMPLETION DIVISION
SEP 16 1981