

22-7-19W


WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY  
508 East Murdock, Wichita, Kansas

Company- AYLWARD DRLG.  
Farm- Roy "B" No. 2

SEC. 22 T. 7 R. 19W  
NW SE NE

Total Depth. 3404  
Comm. 9-9-65 Comp. 9-15-65  
Shot or Treated.  
Contractor. Aylward Drlg.  
Issued. 2-5-66

County Rooks  
KANSAS



Elevation. 1931' KB

Production. 20 BOPD, 28% wtr.

CASING:

8 5/8" @ 1153' w/ 550 sx.  
5 1/2" @ 3394' w/ 100 sx.

Figures Indicate Bottom of Formations.

sand & clay	40
rock	65
sand	75
blue shale	865
shale	915
sand	1072
red bed, red rock w/shale	1154
red bed	1460
Anhydrite	1490
shale & shells	1605
shale	1870
lime & shale	2950
lime	3400
TD.	

GEOLOGICAL TOPS:

Topoka	2871
Heebner	3075
Toronto	3099
Lansing	3114
Conglomerate	3387
Arbuckle	3393

DST 3040-60 Opn. 1 hr., rec. 520' SW  
IBHP 1066#/20" - FBHP 1006#/30" FP 44-260#.

DST 3260-970 Opn. 1 hr. rec. 30' mud  
IBHP 365#/30" - FBHP 104#/30" FP 29-37# .

DST 3376-3400 Opn. 1 hr. Rec. 125'  
Hvy O&GCM, 60' gas in pipe, IBHP 907#/30"  
FBHP 839#/30" FP 29-67#.