

WELL LOG BUREAU - KANSAS GEOLOGICAL SOCIETY

508 E. Murdock,

Wichita, Kansas

Company - HARRY GORE OIL CO.

Farm - Cramm

No. 2

15-163-02666
SEC. 28 T. 7 R. 19W
NE NE NE

Total Depth. 3422

Comm. 7-18-51

Comp. 7-30-51


Shot or Treated.

Contractor. Strain Drlg.

Issued. 9-1-51

County. Rooks

KANSAS



Elevation. 1920 D.F.

Production. Dry

CASING:

8 5/8" 185' cem. w/135 sx.

5 1/2" 3382' cem. w/150 sx.

Figures Indicate Bottom of Formations.

lime & clay	65
shale	740
sand	830
shale	1100
sand	1320
shale sand, redbed	1400
shale, redbed	1428
anhyd.	1465
shale	1525
shale & shells	1755
shale & lime	1895
lime	2055
lime & shale	2225
lime	2370
lime & shale	2925
lime	3010
shale & lime	3060
lime	3370
congl.	3382
Arb.	3390
Arb.	3422
Total Depth	

Tops: From Rig floor

Anhyd.	1428
Topeka	2863
Heebner	3067
Dodge	3082
Lansing-K.C.	3096
Base K.C.	3327
Congl.	3371
Arb.	3380

All Meas. rotary bushings

DST Johnston Testing Co.

3245-3290' tool open at 2:40
to 3:10 a.m. Rec. 510' mud &
trace of oil. BHP 15 min. 1420 $\frac{1}{2}$ lbs.

3241-3290' Tool open at 6:55 to
7:55 p.m. Rec. 65' mud 180' oil & gas
cut mud. BHP 15 min. 1000 $\frac{1}{2}$ lbs.

3290-3335' Tool open 30 min.
Rec. 20' drlg. mud. BHP 350 $\frac{1}{2}$ lbs.

Ran Schlumberger to T.D.