

5-7-20W <sup>PI</sup>  
*and*

TYPE

**AFFIDAVIT OF COMPLETION FORM**

ACO-1 WELL HISTORY

Compt. \_\_\_\_\_

SIDE ONE

(Rules 82-3-130 and 82-3-107)

DOCKET NO. NP \_\_\_\_\_

This form shall be filed with the Kansas Corporation Commission, 200 Colorado Derby Building, Wichita, Kansas 67202, within ninety (90) days after the completion of a well, regardless of how the well was completed.

FOR INFORMATION REGARDING THE NUMBER OF COPIES TO BE FILED AND APPLICATIONS REQUIRING COPIES OF ACO-1 FORMS SEE PAGE TWO (2), SIDE TWO (2) OF THIS FORM.

F  Letter requesting confidentiality attached.

C  Attach ONE COPY of EACH wireline log run (i.e. electrical log, sonic log, gamma ray neutron log etc.)\*\*\*Check here if NO logs were run \_\_\_\_\_.

PLEASE FILL IN ALL INFORMATION. IF NOT AVAILABLE, INDICATE. IF INFORMATION LATER BECOMES AVAILABLE, SUBMIT BY LETTER.

LICENSE # 7419 EXPIRATION DATE 8406  
OPERATOR Alcona Oil Company API NO. 15-163-22,239  
ADDRESS Rt. 2, Box 51 COUNTY Rooks  
Stockton, Kansas 67669 FIELD \_\_\_\_\_

\*\* CONTACT PERSON Dean LeSage PROD. FORMATION ARB, L/KC  
PHONE 913-839-4434 \_\_\_\_\_ Indicate if new pay.

PURCHASER Farmland Industries LEASE LeSage "B"  
ADDRESS 920 Union Center Bldg., Wichita, Ks. WELL NO. #1

DRILLING CONTRACTOR Pioneer Drilling Company, Inc. 330 Ft. from N Line and  
ADDRESS 308 West Mill 330 Ft. from E Line of ~~XXXX~~  
Plainville, Ks 67663 the (Qtr.) SEC 5 TWP 7 RGE 20 (W).

PLUGGING CONTRACTOR \_\_\_\_\_  
ADDRESS \_\_\_\_\_

WELL PLAT (Office Use Only)  
KCC   
KGS   
SWD/REP \_\_\_\_\_  
PLG. \_\_\_\_\_  
NGPA \_\_\_\_\_

		5	

TOTAL DEPTH 3700' PBTD \_\_\_\_\_  
SPUD DATE 12-26-83 DATE COMPLETED 1-24-84  
ELEV: GR 2206' DF 2209' KB 2211'

DRILLED WITH (~~XXXXX~~) (ROTARY) ~~XXXXX~~ TOOLS.  
DOCKET NO. OF DISPOSAL OR REPRESSURING WELL BEING USED TO DISPOSE OF WATER FROM THIS LEASE \_\_\_\_\_

Amount of surface pipe set and cemented 8 5/8" @ 260' DV Tool Used? \_\_\_\_\_

TYPE OF COMPLETION THIS AFFIDAVIT APPLIES TO: (Circle ONE) - Oil, Shut-in Gas, Gas, Dry, Disposal, Injection, Temporarily Abandoned. If OWWO, indicate type of re-completion \_\_\_\_\_. Other completion \_\_\_\_\_. NGPA filing \_\_\_\_\_.

ALL REQUIREMENTS OF THE STATUTES, RULES AND REGULATIONS PROMULGATED TO REGULATE THE OIL AND GAS INDUSTRY HAVE BEEN FULLY COMPLIED WITH.

A F F I D A V I T

Dean LeSage - owner, being of lawful age, hereby certifies that:

I am the Affiant, and I am familiar with the contents of the foregoing Affidavit. The statements and allegations contained therein are true and correct.

Side TWO OPERATOR Alcona Oil Company LEASE NAME LeSage "B" SEC 5 TWP 7 RGE 20 (W) XERO  
 WELL NO #1

FILL IN WELL INFORMATION AS REQUIRED:

Show all important zones of porosity and contents thereof; cored intervals, and all drill-stem tests, including depth interval tested, cushion used, time tool open, flowing and shut-in pressures, and recoveries.

Show Geological markers, logs run, or other Descriptive information.

Formation description, contents, etc.	Top	Bottom	Name	Depth
<input checked="" type="checkbox"/> Check if no Drill Stem Tests Run. Check if samples sent Geological Survey.				
<input checked="" type="checkbox"/> Will send samples.			Anh	1799 +412
			Top	3180 -969
sand and shale	0'	200'	Heeb	3393 -1182
sand and shale	200'	260'		
shales and sand	260'	480'	Tor	3414 -1203
shales and sands	480'	1705'		
shale and sand	1705'	1801'	L/KC	3428 -1217
anhydrite	1801'	1828'		
lime and shale	1828'	2335'	BKC	3621 -1410
shales and lime	2335'	2520'		
lime and shale	2520'	2763'	Arb	3659 -1448
lime and shale	2763'	2941'		
lime and shale	2941'	3120'		
lime and shale	3120'	3288'		
lime and shale	3288'	3427'		
lime and shale	3427'	3540'		
lime and shale	3540'	3683'		
lime and shale	3683'	3700'		
	3700'	R.T.D.		

If additional space is needed use Page 2

Report of all strings set — surface, intermediate, production, etc. **CASING RECORD (New) or ~~XXXX~~**

Purpose of string	Size hole drilled	Size casing set (in O.D.)	Weight lbs/ft.	Setting depth	Type cement	Sacks	Type and percent additives
Surface Casing	12 1/4"	8 5/8"	20#	260'	60-40pos	150	3%cc 2%gel
Production	7 7/8"	4 1/2"	10.5#	3699'	ASC	150	500 gal mud flush

LINER RECORD			PERFORATION RECORD		
Top, ft.	Bottom, ft.	Sacks cement	Shots per ft.	Size & type	Depth interval

TUBING RECORD		
Size	Setting depth	Pecker set at