

7- 7- 20W


WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY
508 East Murdock, Wichita, Kansas

Company- IMPERIAL OIL OF KANS., INC.
Farm- Western Auto No. 2

SEC. 7 T. 7 R. 20W
C NE SW

Total Depth. 3635'
Comm. 1-6-61 Comp. 1-16-61
Shot or Treated.
Contractor.
Issued. 3-25-61

County Rocks
KANSAS



CASING:
8 5/8" 188' cem w/150 sx.

Elevation. 2151' RB

Production. Dry

Figures Indicate Bottom of Formations.

surface clay & shale	188
shale, sand & shells	870
shale & sand	1240
Dakota sand	1455
red bed & shale	1724
Anhydrite	1758
shale & shells	1845
shale & lime	3223
lime	3635
Total Depth	

TOPS: SAMPLE

Topeka	3149
Heebner	3350
Toronto	3371
Lansing	3387
Base Kansas City	3582
Arbuckle	3620

DST #1 3381-3400', op 1 hr, rec. 10' mud,
IBHP 475#/20 min, FBHP 685#/30 min.
Flow pressures 0#.

DST #2 3412-34', op 1 hr, rec. 10' mud,
BHP 0#.

DST #3 3431-53', op 1 hr, rec. 10' mud,
All pressures 0#.

DST #4 3450-73', op 1 hr, rec. 10' mud,
All pressures 0#.

DST #5 3500-87', op 1 hr, rec. 20' mud,
IBHP 215#, FBHP 110#/20 min.

DST #6 3623-35', op 1 hr, rec. 30' mud
w/scum of oil, IBHP 45#, FBHP 30#.