

WELL LOG BUREAU--KANSAS GEOLOGICAL SOCIETY
412 Union National Bk. Bldg., Wichita, Kansas

15-163-00240


Company - ALADDIN PETROLEUM CORPORATION
Farm - Cahill No.1

SEC. 13 T. 7 R.20W
NE NE NE

Total Depth. 3544
Comm. 5-6-49 Comp. 6-1-49
Shot or Treated.
Contractor. H & H Drilling Co.
Issued. 6-25-49

County. Rooks

KANSAS



8 5/8" CASING: 180' cem w/150 sx
5 1/2" 3515' cem w/75 sx

Elevation. 2040

Production. Dry

Figures Indicate Bottom of Formations.
clay 20 Circ. for samples @
shale, blue 180 3520 1 hr good odor
shale 620 3520 Rotary Total Depth
shale, shells, sand 1090
dakota sand 1300
shale, shells 1510
shale, sand 1582
anhydrite 1621
shale, shells 1750
shale, shells 2065
shale, shells 2110
lime 2260
shell 2384
shale 2550
shale, lime 2645
shale, lime 2774
shale 2913
shale, lime 3036
lime 3108
shale 3184
lime, shale 3251
limo 3300
shale, lime 3351
limo 3400
limo 3494
limo, shale 3512
limo arbuckle 3520
limo 3544
Total Depth

TOPS:

Hoebner 3221
Dodgo 3245
Kansas City 3269
Arbuckle Ero. 3509
Arbuckle True 3512

Remarks:

Slope test @ 500' OK SIM-OK
Slope Test @ 1000' OK
Slope Test @ 1500' OK
Trip @ 1605', Bit #1 made
1520' in 14 hr OB with Bit #2
SIM-OK
Jetted pits. Slope Test @ 2000' OK
Trip @ 2320 Bit #2 made 715' in
22 1/2 hr OB with Bit #3
Jetted pit. Slope Test @ 2500' OK
SIM-OK 1/2 Trip, Bit #3 made 325'
8 hr. 1/2 Trip. OB with Bit #4
Jetted pits
Jetted pits twice. Slope Test @
3000' OK 1/2 Trip. Bit #4 made
464 in 29 hr & 15 min. SIM @ 3162-OK
1/2 Trip. Bit #5 made 192' in 22 hr
30 min. 1/2 Trip. Trip @ 3488
Bit #6 made 188' in 28 hr OB with
Bit #7