

18-7-20W

WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY

508 East Murdock,

Wichita, Kansas

15-163-02634

Company- IMPERIAL OIL OF KANSAS, INC.
 Farm- Le Sage No. 2

SEC. 18 T. 7 R. 20W
 C NW NE

Total Depth. 3673'

Comm. 11-1-60

Comp. 11-11-60


Shot or Treated.

Contractor.

Issued. 1-14-61

County Rocks

KANSAS



CASING:
 8 5/8" 190' cem w/150 sx.

Elevation. 2143' KB

Production. Dry

Figures Indicate Bottom of Formations.

surface clay & sand	190
shale & shells	630
shale & sand	1230
Dakota sand	1440
shale & redbed	1705
shale & shells	1720
Anhydrite	1752
shale & shells	2180
shale & lime	3305
lime	3673 RTD
Total Depth	

TOPS: SAMPLE

Anhydrite (scout)	1720
Topeka	3133
Heebner	3338
Toronto	3360
Lansing	3376
Base Kansas City	3575
Marmaton Lime	3610
Arbuckle	3648

DST #1 3334-69', op 30 mins, rec. 15'
 mud, IBHP 1030#, FBHP 0#.

DST #2 3400-20', op 45 mins, rec. 5' of
 mud, BHP 0#.

DST #3 3419-42', op 30 mins, rec. 10'
 mud, BHP 0#.

DST #4 3440-53', op 1 hr, rec. 50' of
 oil spotted mud, IBHP 520#, FBHP 0#.

DST #5 3452-60', op 30 mins, rec. 10'
 of mud, BHP 0#.

DST #6 3572-3616', op 30 mins, rec. 60'
 mud, BHP 0#.