

27-7-20W P2

TYPE

AFFIDAVIT OF COMPLETION FORM

ACO-1 WELL HISTORY

SIDE ONE

Compt. _____

Two (2) copies of this form shall be filed with the Kansas Corporation Commission, 200 Colorado Derby Building, Wichita, Kansas 67202, within thirty (30) days after the completion of a well, regardless of how the well was completed.

F Attach separate letter of request if the information is to be held confidential. If confidential, only file one copy. Information on Side One will be of public record and Side Two will then be held confidential.

Applications must be made on dual completion, commingling, salt water disposal, injection and temporarily abandoned wells.

C Attach one copy only wireline logs (i.e. electrical log, sonic log, gamma ray neutron log, etc.). (Rules 82-2-105 & 82-2-125) KCC# (316) 263-3238.

LICENSE # 5131 EXPIRATION DATE 6-30-83

OPERATOR Thunderbird Drilling, Inc. API NO. 15-163-21,829

ADDRESS P.O. Box 18407 COUNTY Rooks

Wichita, Kansas 67218 FIELD WC

** CONTACT PERSON Gloria DeJesus PROD. FORMATION

PHONE (316) 685-1441

PURCHASER LEASE HAMEL

ADDRESS WELL NO. 1

WELL LOCATION SW NW NW

DRILLING Thunderbird Drilling, Inc. 330 Ft. from West Line and

CONTRACTOR 990 Ft. from North Line of

ADDRESS P.O. Box 18407 the NW (Qtr.) SEC 27 TWP 7S RGE 20W

Wichita, Kansas 67218

PLUGGING Thunderbird Drilling, Inc. WELL PLAT

CONTRACTOR Same

ADDRESS

TOTAL DEPTH 3520 PBTD

SPUD DATE 10/16/82 DATE COMPLETED 10/27/82

ELEV: GR 1975' DF KB 1980

DRILLED WITH (XXXX) (ROTARY) XXXX TOOLS.

DOCKET NO. OF DISPOSAL OR REPRESSURING WELL BEING USED TO DISPOSE OF WATER FROM THIS LEASE

Amount of surface pipe set and cemented 371'w/225 sx DV Tool Used? no

THIS AFFIDAVIT APPLIES TO: (Circle ONE) - Oil, Gas, Shut-in Gas, (Dry), Disposal, Injection, Temporarily Abandoned, OWWO. Other

ALL REQUIREMENTS OF THE STATUTES, RULES AND REGULATIONS PROMULGATED TO REGULATE THE OIL AND GAS INDUSTRY HAVE BEEN FULLY COMPLIED WITH.

RECEIVED
STATE CORPORATION COMMISSION

DEC 10 1982

A F F I D A V I T

Burke Krueger, being of lawful age, hereby certifies that:

I am the Affiant, and I am familiar with the contents of the foregoing Affidavit. The statements and allegations contained therein are true and correct.

KA RI

SIDE TWO

ACO-1 WELL HISTORY

OPERATOR Thunderbird Drilling, Inc. LEASE HamelSEC. 27 TWP. 7S RGE. 20WWELL NO. 1

FILL IN WELL INFORMATION AS REQUIRED:

Show all important zones of porosity and contents thereof; cored intervals, and all drill-stem tests, including depth interval tested, cushion used, time tool open, flowing and shut-in pressures, and recoveries.

SHOW GEOLOGICAL MARKERS, LOGS RUN, OR OTHER DESCRIPTIVE INFORMATION.

FORMATION DESCRIPTION, CONTENTS, ETC.	TOP	BOTTOM	NAME	DEPTH
Check if no Drill Stem Tests Run.				
DST #1, 3111-3170/30-45-60-45, rec. 1125' mw w/few spks oil, FP 126-565#, BHP 1164-1164#			LOG TOPS:	
DST #2, 3194-3220/30-45-30-45, rec. 15 mud, FP 58-58# BHP 1116-1116#			Anhydrite	1540+ 440
DST #3, 3318-3365/30-30-30-30, rec. 10 mud, FP 58-58#, BHP 903-806#			B/Anhydrite	1572+ 408
DST #4, 3358-3400/30-45-30-45, rec. 5' mud, BHP 127-88# BP 49-49#			Heebner	3161-1181
DST #5, 3425-3473/30-45-30-45, rec. 15 mud, FP 68-68# BHP 362-186#			Toronto	3182-1202
			Lansing	3199-1219
			BKC	3404-1424
			Arbuckle	3448-1468
			LTD	3518-1538
			RTD	3520-1540
<u>Description</u>	<u>From</u>	<u>To</u>		
Surface Hole	0	371		
Shale & Sand	371	450		
Shale w/snd strks	450	1065		
Sand	1065	1275		
Shale & Red Bed	1275	1541		
Anhydrite	1541	1575		
Shale	1575	1655		
Shale & Lime	1655	1960		
Shale	1960	2225		
Shale & Lime	2225	2960		
Lime & Shale	2960	3170		
Lime	3170	3520		
R.T.D.				

If additional space is needed use Page 2. Side 2

Report of all strings set— surface, intermediate, production, etc. CASING RECORD (New) or ~~Used~~

Purpose of string	Size hole drilled	Size casing set (in O.D.)	Weight lbs/ft.	Setting depth	Type cement	Sacks	Type and percent additives
Surface	12 3/4	8 5/8"	24#	371'	com	225	2% gel, 3% cc.

LINER RECORD

PERFORATION RECORD

Top, ft.	Bottom, ft.	Sacks cement	Shots per ft.	Size & type	Depth interval
TUBING RECORD					
Size	Setting depth	Packer set at			