

JOHN O. FARMER, INC.

P.O. Box 352

Russell, KS 67665

(785) 483-3144

Distribution:

Presley Petroleum

Terry Marple

Penguin Petroleum

Gerald N. Furseth

Robert Schmidt

Kirk Rundle

Aven Weaverling

James Devlin Living Trust

BENOIT A #1

1080' FSL & 730' FWL

Sec. 32-7S-20W

Rooks County Kansas

1962 'G.L.

1970 'K.B.

Drilling Contractor:

Discovery Drilling - Rig #1

Cell (785) 635-1201

Toolpusher - Cliff Mayfield

Cell

Geologist - Matt Dreiling

Cell (785) 483-7835

Home (785) 628-7954

Office (785) 483-3144

API #15-163-23424

TIGHT HOLE - DO NOT RELEASE INFORMATION8/31/2004

Moved in Discovery Rig #1-spud @ 1:00 PM; drilled
212' of 12 1/4" hole, ran 5 Joints New 23# 8 5/8" (201.44)
Set at 211.44', Cement by Allied w/150 sx common 2% Gel,
& 3% cc (did circ.) Drilled plug @ 1:30a.m.

9/1/2004

2368', drilling

9/2/2004

3145', drilling

DST #1- 3212'-3250' (Lansing C)

30"- 30"- 60"-60"

IF: BOB in 20", Surface blow on shut in

FF: BOB in 45", No blow on shut in

REC: 5' Clean Oil**25' Muddy Water (25% Mud, 75% Water)****250' Saltwater Chlorides 53,000****280' Total Fluid**

FP: 29-76#, 87-139#

SIP: 235-242#

HP: 1581-1494#

BHT: 107

9/3/2004

3278', running DST #2

DST #2- 3239'-3278' (Lansing E)

30"- 30"- 30"- 45"

IF: BOB in 8", 1/4" blow on shut in

IF: BOB in 5", 1/4" blow on shut in

REC: 680' Gas in Pipe**124' GMO (10% Gas, 20% Mud, 70% Oil)****248' MGO (7% Mud, 15% Gas, 78% Oil) 35 Gravity****372' Total Fluid**

FP: 26-91#, 103-150#

SIP: 813-792#

HP: 1535-1506#

BHT: 107

DST #3- 3302'-3390' (Lansing H thru K)

30"- 30"- 30"- 30"

IF: Surface built to 1/4", no blow on shut in

FF: No Blow, no blow on shut in

REC: 2' Drilling Mud

FP: 48-51#, 48-51#

SIP: 186-115#

HP: 1589-1585#

BHT: 103

9/4/2004

3445', drilling

DST #4- 3379'-3452' (top 16' of Arbuckle)

30"- 30"- 30"- 45"

IF: Surface built to 1", no blow on shut in

FF: No Blow, no blow on shut in

REC: 15' Drilling Mud

FP: 49-61#, 55-59#

SIP: 408-457#

HP: NA-1617#

BHT: 109

Baird Oil Benoit #1-31 31-7S-20W Rooks Co. 2004 KB			Estim. from 3D Seismic	JOHN O. FARMER, INC. Benoit A #1 1970 Sample E-Log			
Anhydrite	1559	445	442	1524	446	1524	446
Topeka	2970	-966		2943	-973	2944	-974
Heebner	3173	-1169	-1174	3150	-1180	3150	-1180
Toronto	3196	-1192		3172	-1202	3173	-1203
Lansing	3212	-1208		3188	-1218	3189	-1219
Stark Sh	3388	-1384		3363	-1393	3364	-1394
B/KC	3414	-1410		3390	-1420	3389	-1419
Arbuckle	3446	-1442		3436	-1466	3438	-1468
RTD	3484	-1480		3498	-1528		
LTD	3484	-1480				3500	-1530