32-7s-21w



TRILOBITE TESTING, INC.

DRILL STEM TEST REPORT

Prepared For: **American Warrior, Inc.**

PO Box 399
Garden City KS 67846

ATTN: Al Downing

32-7s-21w/Graham KS

Tyner-Stehno 1-32

Start Date: 2006.04.01 @ 07:37:49
End Date: 2006.04.01 @ 13:33:02
Job Ticket #: 24315 DST #: 1

15-065-23161-00-00

RECEIVED
MAY 22 2006
KCC WICHITA

Trilobite Testing, Inc
PO Box 362 Hays, KS 67601
ph: 785-625-4778 fax: 785-625-5620

DRILL STEM TEST REPORT

TRILOBITE TESTING, INC.

American Warrior, Inc.

PO Box 399
Garden City KS 67846

ATTN: Al Dow ning

Tyner-Stehno 1-32

32-7s-21w/Graham KS

Job Ticket: 24315 **DST#: 1**

Test Start: 2006.04.01 @ 07:37:49

GENERAL INFORMATION:

Formation: **LKC "E-F"**
Deviated: No Whipstock: ft (KB)
Time Tool Opened: 09:14:47
Time Test Ended: 13:33:02

Test Type: Conventional Bottom Hole
Tester: Brian Fairbank
Unit No: 24

Interval: 3424.00 ft (KB) To 3445.00 ft (KB) (TVD)
Total Depth: 3445.00 ft (KB) (TVD)
Hole Diameter: 7.88 inches Hole Condition: Good


Reference Elevations: 2143.00 ft (KB)
2135.00 ft (CF)
KB to GR/CF: 8.00 ft

Serial #: 6769 **Inside**

Press@RunDepth: 70.00 psig @ 3425.01 ft (KB)
Start Date: 2006.04.01 End Date: 2006.04.01
Start Time: 07:37:49 End Time: 13:33:02

Capacity: 7000.00 psig
Last Calib.: 2006.04.01
Time On Btm: 2006.04.01 @ 09:14:32
Time Off Btm: 2006.04.01 @ 12:13:47

TEST COMMENT: IFP w eak to good blow surface 6"
ISI no blow back
FFP w eak to fair blow surface 5"
FSI no blow back 30 min w eak surface blow back



PRESSURE SUMMARY

Time (Min.)	Pressure (psig)	Temp (deg F)	Annotation
0	1692.46	99.23	Initial Hydro-static
1	11.92	98.77	Open To Flow (1)
44	44.85	104.53	Shut-In(1)
90	770.65	103.35	End Shut-In(1)
90	46.60	103.19	Open To Flow (2)
135	70.00	104.41	Shut-In(2)
179	652.35	105.11	End Shut-In(2)
180	1599.41	105.66	Final Hydro-static

Recovery

Length (ft)	Description	Volume (bbl)
5.00	mud 100%	0.02
110.00	WM 30% W, 70% M	1.32

Gas Rates

	Choke (inches)	Pressure (psig)	Gas Rate (Mcf/d)

TRILOBITE TESTING, INC.

DRILL STEM TEST REPORT

TOOL DIAGRAM

American Warrior, Inc.

PO Box 399
Garden City KS 67846

ATTN: Al Dow ning

Tyner-Stehno 1-32

32-7s-21w/Graham KS

Job Ticket: 24315 **DST#: 1**

Test Start: 2006.04.01 @ 07:37:49

Tool Information

Drill Pipe:	Length:	3406.00 ft	Diameter:	3.80 inches	Volume:	47.78 bbl	Tool Weight:		2200.00 lb
Heavy Wt. Pipe:	Length:	0.00 ft	Diameter:	0.00 inches	Volume:	0.00 bbl	Weight set on Packer:		25000.00 lb
Drill Collar:	Length:	30.00 ft	Diameter:	2.25 inches	Volume:	0.15 bbl	Weight to Pull Loose:		75000.00 lb
					Total Volume:	47.93 bbl	Tool Chased		0.00 ft
Drill Pipe Above KB:		32.00 ft					String Weight:	Initial	51000.00 lb
Depth to Top Packer:		3424.00 ft						Final	58000.00 lb
Depth to Bottom Packer:		ft							
Interval betw een Packers:		21.02 ft							
Tool Length:		41.02 ft							
Number of Packers:		2	Diameter:	6.75 inches					

Tool Comments:

Tool Description	Length (ft)	Serial No.	Position	Depth (ft)	Accum. Lengths	
S.I. Tool	5.00			3409.00		
HYD S.I. Tool	5.00			3414.00		
Packer	5.00			3419.00	20.00	Bottom Of Top Packer
Packer	5.00			3424.00		
Stubb	1.00			3425.00		
Recorder	0.01	6769	Inside	3425.01		
Perforations	17.00			3442.01		
Recorder	0.01	13548	Outside	3442.02		
Bullnose	3.00			3445.02	21.02	Bottom Packers & Anchor
Total Tool Length:	**41.02**					

TRILOBITE TESTING, INC.

DRILL STEM TEST REPORT

FLUID SUMMARY

American Warrior, Inc.

PO Box 399
Garden City KS 67846

ATTN: Al Downing

Tyner-Stehno 1-32

32-7s-21w/Graham KS

Job Ticket: 24315 **DST#: 1**

Test Start: 2006.04.01 @ 07:37:49

Mud and Cushion Information

Mud Type:	Gel Chem	Cushion Type:		Oil API:	deg API
Mud Weight:	9.00 lb/gal	Cushion Length:	ft	Water Salinity:	60000 ppm
Viscosity:	50.00 sec/qt	Cushion Volume:	bbl		
Water Loss:	8.77 in³	Gas Cushion Type:			
Resistivity:	ohm.m	Gas Cushion Pressure:	psig		
Salinity:	2000.00 ppm				
Filter Cake:	inches				

Recovery Information

Recovery Table


Length ft	Description	Volume bbl
5.00	mud 100%	0.025
110.00	WM 30% W, 70% M	1.315

Total Length: 115.00 ft Total Volume: 1.340 bbl

Num Fluid Samples: 0 Num Gas Bombs: 0 Serial #:

Laboratory Name: Laboratory Location:

Recovery Comments:


Pressure vs. Time
6769 Pressure
6769 Temperature
Initial Hydro-static
Final Hydro-static
End Shut-In(1)
End Shut-In(2)
Open To Flow(1)
Shut-In(1)
Open To Flow(2)
Shut-In(2)
Pressure (psig)
Temperature (deg F)
1750
1500
1250
1000
750
500
250
0
105
100
95
90
85
80
75
70
65
60
55
50
9AM
12PM
1 Sat Apr 2006
Time (Hours)