

WELL LOG BUREAU - KANSAS GEOLOGICAL SOCIETY
508 East Murdock,
Wichita, Kansas

6-7-21W


15-065-00221

Company- B & R DRILLING, INC.
Farm- Ridgley No. 1

SEC. 6 T. 7 R. 21W
SW SW SW

Total Depth. 3810
Comm. 12-9-51 Comp. 12-24-51
Shot or Treated.
Contractor.
Issued. 2-9-52

County Graham
KANSAS



CASING:
8 5/8" 282' cem w/200 sx
5 1/2" 3750.09' cem w/75 sx

Elevation. 2233
2238 (2nd)
Production. dry

Figures Indicate Bottom of Formations.

surfaced clay	18
clay, sand	60
sand, gravel	110
sand, shale	160
shale, shells	394
shale	690
shale, shells	825
shale, sand	960
shale, shells, sand	1110
shale, shells	1244
shale, shells, sand	1330
shale, shells, red bed	1370
sand	1575
shale, red bed	1839
anhydrite	1879
shale, shells	1903
red bed, shale, shells	2100
shale, shells	2230
shale, lime	2665
shale	2685
shale, lime	3255
lime	3288
lime, chert	3314
lime	3446
shale	3455
lime, shale	3470
lime	3756
lime	3810
Total Depth	

Tops: Scout:

Topeka	3235
Oread	3388
Heebner	3448
Toronto	3459
Lansing	3471
Lansing-Kansas City	3670
Marmaton	3715
Sand	3727
Arbuckle	3751