

WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY
508 East Murdock,
Wichita, Kansas


SEC. 6 T. 7 R. 22W
C SW NE

Company- MURFIN-RAINS & WILLIAMSON
Farm- Mildrexter "B" No. 1

15-065-00580

County Graham
KANSAS

Total Depth. 4050'
Comm. 10-13-58 Comp. 10-23-58
Shot or Treated.
Contractor. Murfin Drlg.
Issued. 1-17-59



Elevation. 2398' DE

Production. Pot. 326 BOPD

CASING:

8 5/8" 275' cem w/100 sx.
5 1/2" 3830' cem w/125 sx.

Figures Indicate Bottom of Formations.

surface hole	275
shale	400
shale-shells	990
shale-sand	1050
shale	1535
sand	1775
red bed - shale	1970
shale	2025
Anhydrite	2065
shale - shells	2300
shale - lime - shells	2510
lime - shale	3635
lime	3855
lime - shale	3915
lime	3942
lime - shale	4035
lime	4050
Total Depth	

TOPS:

Topeka	3402
Heebner	3598
Toronto	3622
Lansing-Kansas City	3638
Base Kansas City	3832
Conglomerate	3938
Arbuckle	3999

Perf. 3790-3792', E gun. Hole filled
up 350'/15 min.

Perf. 3780-3786, 25 holes, filled up
200'/15 min.

Acidized w/3000 gal. of 15% regular,
350# max. pressure.

Perf. from 3759-64, 25 holes, E gun.

Acidized with 3000 gal. 15% regular,
max. pressure 200#.