

WELL LOG BUREAU - KANSAS GEOLOGICAL SOCIETY  
412 Union National Bk. Bldg., Wichita, Kansas

59750


15-065-02700

Company - DAVIS & CHILD MOTOR CO.  
Farm - Scott No. 1.

SEC. 7 T. 7 R. 22 W  
NEc NW

Total Depth. 4000'  
Comm. 11-27-43 Comp. 12-13-43  
Shot or Treated.  
Contractor. H.M. Williams Drlg. Co.  
Issued. 1-1-44

County. Graham  
KANSAS



CASING:  
10" 188'

Elevation. \_\_\_\_\_

Production. Dry

Figures Indicate Bottom of Formations.

shale	40
sand	100
shale & sand	250
shale	756
shale & shells	2210
red rock, shale, shells	2290
shale & shells	2460
shale & lime shells	2510
shale & lime	2970
lime	3025
lime & shale	3085
lime	3125
lime hd	3160
lime	3170
lime & shale	3240
lime	3340
lime & shale	3485
lime	3530
lime & shale	3600
lime	3810
shale & lime	3950
lime	4000
Total Depth.	

Tops: Anhydrite	1975
Topeka Lime	3360
Heebner Shale	3568
Lansing Lime	3593
Base K.C. Lime	3804
Conglomerate	3920
Arbuckle Lime	3946

very slight stains of oil  
in Lansing-K.C. at 3611-14,  
3640-46, 3666-67, 3677-81,  
3744-48, 3765-70, and  
3780-85

In Arbuckle had sft zone in  
dolomite w/blk heavy residue  
3947-55. Cored 3950-54 w/  
100% recovery porous dolo.  
w/blk heavy oil residue.  
Second porous zone in Arb.  
dolo. 3959-63; had little blk  
oil residue

Schlumberger electric survey  
at 4000' or total depth