


WELL LOG BUREAU--KANSAS GEOLOGICAL SOCIETY
508 East Murdock, Wichita, Kansas

Company- MURFIN DRILLING COMPANY
Farm- Fabricius No. 1

SEC. 16 T. 7 R. 22W
NW NW SW

Total Depth. 3895
Comm. 12-30-52 Comp. 1-14-53
Shot or Treated.
Contractor. Murfin Drilling Co.
Issued. 3-14-53

County Graham
KANSAS



Elevation. ²³³² 2335 RB

Production. Dry

CASING:

8 5/8" 170' cem. w/125 sx
5 1/2" 3780' cem. w/100 sx

Figures indicate Bottom of Formations.

shale	800
sand & shale	960
shale	1150
shale & shells	1330
sand	1355
shale	1400
shale & shells	1505
sand & shale	1710
red bed	1980
anhydrite	2009
shale	2300
shale & lime	3333
lime	3497
lime & shale	3548
shale	3552
lime	3780
lime & shale	3824
lime	3875
congl.	3895
Total Depth	

Tops:	
Heebner	3518
Toronto	3542
Lansing	3556
Cherty Congl.	3895

DST: 3628-40 open 30 mins.
strong blow 262' muddy wtr.
BHP 1025 #1 FP 50#.

DST: 3683-91' open 1 hr.
blow for 3 min. 12' of
mud 700# BHP in 15 min.

DST: 3708-20 open 30
min. weak flow 8 min.
rec. 6' of mud BHP 550#
in 15 mins.

DST: 3735-47' 1 hr. moderate
flow throughout test. rec.
60' of gas, 153' of clean
gassy oil 30' of oil & wtr.
cut mud BHP 900# in 15 mins.

Perf. 12 shots 3739-43
1 BWP acid 1000
1 BOPH plus 10 BWP for 5 hrs.

Perf. 24 shots-3594 3602 HFW
Re-perf. at 3594-3602 HFW

Good show 3594-98'