

17-7-22W

WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY
508 East Murdock, Wichita, Kansas


15-065-00784

Company- IMPERIAL OIL OF KANSAS, INC.
Farm- Worcester "A" No. 1

SEC. 17 T. 7 R. 22W
C SE SE

Total Depth. 3790'
Comm. 9-10-59 Comp. 9-19-59
Shot or Treated.
Contractor.
Issued. 2-13-60

County Graham
KANSAS



8 5/8" CASING:
222' cem. w/200 sx.

Elevation. 2360.1 RB

Production. Dry

Figures indicate Bottom of Formations.

sand & shale	1530
Dakota sand	1730
shale & red bed	1983
anhydrite	2015
shale & shells	2130
shale	2300
shale & lime	2640
lime	2730
lime & shale	3520
lime	3790RTD
Total Depth	

TOPS	SCOUT	SAMPLE
Anhydrite	1977	
Ft. Riley	2561	
Topeka		5298
Heebner	3543	3543
Toronto	3569	3569
Lansing	3584	3584
Base Kansas City		3784
No Electric Log Run		

DST #1 3604-23 Open 1 hr. Recovered
1270' muddy salt water. BHP 990#

DST #2 3626-38 Open 1 hr. Recovered
2050' muddy salt water. BHP 1230#

DST #3 3652-59 Open 1 hr. Recovered
660' muddy salt water with a scum
of oil. BHP 1050#

DST #4 3694-3725 Open 1 hr.
Recovered 10' mud. BHP 0#

DST #5 3738-55 Open 2 hrs.
Recovered 75' oil cut muddy salt
water. BHP 1030#