

WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY

508 East Murdock,

Wichita, Kansas

32-7-22W

Company-ANDERSON-PRICHARD OIL CORPORATION
Farm- Jones No. 1


SEC. 32 T. 7 R. 22W
SE SE SW

15-065-03320

Total Depth. 3766
Comm. 7-17-53 Comp. 7-28-53
Shot or Treated.
Contractor. Glenn W. Peel
Issued. 9-12-53

County Graham

KANSAS



Elevation 2172 RB

Production. 148 bbls.

Figures indicate Bottom of Formations.

surface clay & sand 210
shab & sand 1550
shale 1745
anhydrite 1775
shale 2010
lime & shale 2200
shale 2495
lime & shale 2995
lime 3766
Total Depth

TOPS:
Anhydrite 1744
Topeka 3116
Heebner 3326
Toronto 3347
Lansing 3364
Weath. Arbuckle 3705
Arbuckle 3736

DST #1: 3413-45, op. 1 hr.,
strong blow, recov. . . .
1045' MSW, BHP 1310#
DST #2: 3522-35, op. 1 hr.,
mod. blow, recov. 200'
HOCM plus 100' mdy oil,
BHP 1140#.
DST #3: 3536-56, op. 1 hr.,
lgt blow for 32 min.,
recov. 75' mud w/ few
spots oil, BHP 960#.

MICT, swbd. mud and CO to 3580'. Perf.
3529-33 W/6 shaped charges per ft. Bailed
1/2 BOPH w/ tr. wtr. for 3 hrs. Az. w/500
gals. max. press. 100#, min. press. 50#
Swbd. off load & swbd. 80 BO w/ tr. wtr.
in 16 hrs., last 6 hrs. of test swbd. @ rate
of 5 1/2 BOPH w/ tr. wtr. RT&R, POP. P. 92 . . .
BO, 0.8% wtr in 24 hrs. P. 78 BO in 24
hrs. P. 100 BO in 24 hrs. P. 45 BO in 14 .
hrs. 8 hr. state test: 149 BOPD plus 0.8% wtr.