

WICHITA BRANCH

OPERATOR:

Ram Petroleum, Inc.

CONTRACTOR:

Abercrombie Drilling, Inc.

WELL NAME:

Jones #1

LOCATION:

NW SE SW Section ³²~~23~~-7S-22W

Graham County, Kansas

SPUD DATE:

April 25, 1978

COMPLETION DATE:

May 1, 1978

0	285	Sand, rock & shale
285	296	Shale & sand
296	1300	Shale
1300	1510	Sand
1510	1759	Shale
1759	1790	Anhydrite
1790	1798	Shale
1798	2425	Shale & sand
2425	2825	Lime & shale
2825	2957	Shale & lime
2957	3343	Lime & shale
3343	3460	Shale & lime
3460	3639	Lime & shale
3639	3728	Shale & lime
3728	3770	Lime
	3770	Rotary Total Depth

Spud hole at 7:30 a.m., April 25, 1978. Drilled 285' of 12 $\frac{1}{4}$ " hole. Ran 7 joints of 8-5/8" - 28# surface casing. Set at 283' K.B. with 175 sacks 60/40 posmix, 2% gel. Plug was down at 7:00 a.m., April 26, 1978.

T.D. 3770'. Set first plug at 800' with 70 sacks, second plug at 240' with 20 sacks, and plug at 40' with 10 sacks. Cemented with 50/50 posmix, 6% gel. Plug was down at 7:30 p.m., May 1, 1978.

SAMPLE TOPS:

Anhydrite	1759
B/Anhydrite	1790