

WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY
508 East Murdock, Wichita, Kansas

32-7-22W


Company- MORRIS SITRIN & MURFIN DRG. CO.
Farm- Morris No. 1

SEC. 32 T. 7 R. 22W
SE SE SE

15-005-00173

Total Depth. 3766
Comm. 10-10-51 Comp. 10-24-51
Shot or Treated.
Contractor. Murfin Drlg. Co.
Issued. 12-22-51

County Graham KANSAS



CASING:

8" 120'
5" 3760'

Elevation. ~~2179 DE~~
2139(m)
2181 (sand)

Production. 1068 BOPD

Figures Indicate Bottom of Formations.

shale, shells	60
sand	63
shale, shells	115
shale	740
sand	1260
red rock	1323
sand, shale	1550
red bed	1660
red bed, shale	1803
anhydrite	1836
shale	2110
shale, lime	3105
shale	3179
shale, lime	3250
lime	3745
lime, shale	3759
arbuckle	3766 RTD
arbuckle	3772
Total Depth	

Tops:

Anhydrite	1803
Topeka	3164
Heebner	3375
Toronto	3401
Kansas City	3413
Base-Kansas City	3620
Arbuckle	3759

Cable Tool Work:

Drilled to 3772- tr. of oil.
Acidized 1000 gal. - no inc.
Drilled to 3786. Water at 3784'.
Set plug at 3620. Perf. from
3590-3600. 400' free oil in
1 hr. Acidized 1000 gal.