

Operator **John O. Farmer, Inc.** DESIGNATE TYPE OF COMP.: OIL, GAS, DRY HOLE, SWDW, ETC.:

Well No. #1 Lease Name **JoMar** Dry Hole

S 23 T 7S R 23W ^{XX}W

WELL LOG


Show all important zones of porosity and contents thereof; cored intervals, and all drill-stem tests, including depth interval tested, cushion used, time tool open, flowing and shut-in pressures, and recoveries.

SHOW GEOLOGICAL MARKERS, LOGS RUN, OR OTHER DESCRIPTIVE INFORMATION.

FORMATION DESCRIPTION, CONTENTS, ETC.	TOP	BOTTOM	NAME	DEPTH
Clay Sand	-0-	40	Anhydrite	1936 (+347)
Blue Shale	40	202	Heebner	3502 (-1219)
Shale & Sand	202	1450	Toronto	3528 (-1245)
Shale	1450	1489	Lansing	3542 (-1259)
Sand	1489	1699	B/KC	3742 (-1459)
Red Bed	1699	1935		
Anhydrite	1935	1968		
Shale & Shells	1968	2215		
Shale & Lime	2215	3525		
Lime	3525	3749		
<p>DST #1 3640-3710 Tool open 30-45-60-60 with strong blow. Rec: 1340' saltwater FP: 148-675 BHP: 1114-989 Temp: 108</p>				

USE ADDITIONAL SHEETS, IF NECESSARY, TO COMPLETE WELL RECORD.

Date Received _____


 Signature
 President
 Title
 June 22, 1979
 Date