

WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY

508 East Murdock,

Wichita, Kansas

24-7-23W


Company- IMPERIAL OIL OF KANSAS
Farm- Fabricius "B" No. 1

SEC. 24 T. 7 R. 23W
C SW SE

15-065-02954

Total Depth. 3705'
Comm. 7-14-58 Comp. 7-22-58
Shot or Treated.
Contractor. Imperial Oil of Kansas, Inc.
Issued. 10-11-58

County Graham
KANSAS



Elevation. 2250' RB

Production. 1268 BOPD - NW

Figures Indicate Bottom of Formations.

clay and rock	227
shale and sand	1450
dakota sand	1650
red bed and shale	1888
anhydrite	1918
shale and shells	2575
shale	2730
shale and shells	2850
shale and lime	3500
lime	3705' RTD

TOPS:

Anhydrite	1888
Heebner	3456
Toronto	3481
Lansing	3498
Rotary Total Depth	3705

D.S.T. #1 3518-43 Open one hour. Recovered
20' drilling mud, BHP 1150#.

Base Kansas City 3695

D.S.T. #2 3634-48 Open two hrs. Recovered gas to surface in 2 hrs,
1440' clean gassy oil, ICIP 1320#, IF 50#, FF 530#, BHP 1120#.

D.S.T. #3 3650-68 Open one hr. Recovered 1500' gas, 1893' clean
gassy oil, ICIP 1320#, IF 50#, FF 630#, BHP 1170#.

D.S.T. #4 3663-3705 Open one hr. Recovered 8' mud, ICIP 0#,
BHP 50#.