

25-7-23W

WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY
508 East Murdock, Wichita, Kansas


15-005-02959

Company- IMPERIAL OIL OF KANSAS, INC.
Farm- Fabricius "A" No. 5

SEC. 25 T. 7 R. 23W
C NE NE

Total Depth. 3700'
Comm. 10-6-58 Comp. 10-15-58
Shot or Treated.
Contractor. Imperial Oil of Kans.
Issued. 12-20-58

County Graham
KANSAS



Elevation. 2248' RB

Production. 280 BOPD - NW

CASING:

8 5/8" 211' cem w/150 sx.
5 1/2" 3700' cem w/100 sx.

Figures indicate Bottom of Formations.

surface sand & shale	211
shale	1670
shale & shells	1865
Anhydrite	1898
shale & shells	2265
shale	2425
shale & shells	2580
shale & lime	2805
shale	2930
shale & lime	3380
lime	3465
lime & shale	3520
lime	3700 RTD
Total Depth	

TOPS:	SAMPLE	ELECTRIC
Upper Dakota	775	775
Lower Dakota	1380	1380
Anhydrite	1865	1865
Heebner	3452	3454
Toronto	3480	3482
Lansing	3497	3499

DST #1 788-900, op 10 mins., rec. 640' water.

DST #2 1385-1420, op 10 mins., rec. 920' water.

DST #3 3632-70, op 1 hr., rec. 350' gas, 100' oil cut mud, 30' heavy oil cut mud, ICIP 810#, BHP 840#.