

WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY

508 East Murdock,

Wichita, Kansas


15-065-00792

Company- MURFIN DRILLING CO. & RAINS & WILLIAMSON
 Farm- Moore No. 1

SEC. 33 T. 7 R. 23W
 C SE SE

Total Depth. 3825'
 Comm. 7-21-59 Comp. 7-28-59
 Shot or Treated.
 Contractor. Murfin Drlg.
 Issued. 10-17-59

County Graham
 KANSAS



CASING:
 8 5/8" 215' cem w/170 sx.

Elevation. 2324' KB

Production. Dry

Figures Indicate Bottom of Formations.

surface hole	215
shale	1300
iron - sand - shale	1405
shale	1500
sand - shale	1745
red bed - shale	1980
Anhydrite	2015
shale - shells	2420
lime - shale	3590
lime	3825
Total Depth	

TOPS:
 Heebner 3560
 Toronto 3586
 Lansing 3602
 Base Kansas City 3809

DST #1 3595-3610', op 1 hr., rec. 1175'
 salt water. IF 35#, FF 515#, BHP 1150#/
 20 mins.

DST #2 3740-80', op 1 hr., rec. 10' mud.
 All pressures 0#/20 mins.