

WELL LOG BUREAU--KANSAS GEOLOGICAL SOCIETY

508 East Murdock,

Wichita, Kansas


15-065-00589

Company- IMPERIAL OIL OF KANSAS, INC.  
Farm- Fabricius No. 1

SEC. 25 T. 7 R. 23W  
C NE NW

Total Depth. 3890'  
Comm. 3-20-58 Comp. 4-7-58  
Shot or Treated.  
Contractor. Imperial Oil of Kansas  
Issued. 6-28-58

County Graham  
KANSAS



CASING:  
8 5/8" 223' cem w/150 sx.  
5 1/2" 3890' cem w/3890'

Elevation. 2251' RB

Production. 2769 BOPD, no Wtr.

Figures Indicate Bottom of Formations.

surface, clay & sand	223
shale & sand	1440
Dakota sand	1600
shale & shells	1874
Anhydrite	1910
shale & shells	2450
shale & lime	3420
lime	3690
lime & shale	3800
lime	3845
lime & Arbuckle	3890 RTD
Total Depth	

TOPS:	SAMPLE	ELECTRIC LOG
Anhydrite	1874	1876
Heebner	3448	3449
Toronto	3471	3474
Lansing	3490	3492
Base Kansas City	3689	3689
Marmaton	3761	3762
Conglomerate	3825	3826
Arbuckle	3846	3847

DST #1 3513-31, op 2 hrs, rec. 65' mud,  
BHP 1305#.

DST #2 3552-80, op 2 hrs, rec. 250' muddy  
salt water, BHP 1120#.

DST #3 3603-25, op 2 hrs, rec. 35' very  
slightly oil cut mud, BHP 940#.

DST #4 3622-42, op 1 hr, rec. 300' gas, 60'  
heavy oil cut mud, 60' oil, BHP 1230#.

DST #5 3639-58, op 1 hr, gas to surface in  
1 hr, 20 mins. Rec. 1800' oil,  
BHP 1355#.

DST #6 3657-75, op 1 hr, rec. 5' mud,  
BHP 905#.

DST #7 3852-61, op 1 hr, rec. 5' mud,  
BHP 20#.