

MILLER TESTING COMPANY

Box 547

GREAT BEND, KANSAS

Company C. G. DRILLING CO.

Lease and Well No. Charles MOORE #1

County GRAHAM State KANSAS

Date AUGUST 2, 1970

Formation Test No. 1 Total Depth 3760 Elev. 2316 K.B.
Interval Tested 3728 To 3760 Anchor Length 32'
Size Hole 7 7/8 Size Drill Pipe 4 1/2 F.H. Size Packer 6 3/4
Mud Weight _____ Viscosity _____ Water Loss _____ c.c. Bottom Hole Temp. _____ °F
Chokes: Top 1/2 Bottom 1/2 Ticket No. 10745
Length of Drill Collar _____ I. D. _____ Length Flexweight 813 I. D. 2.76

RECOVERY

WEAK BLOW FOR 5 MINUTES.

65 FEET OF VERY SLIGHTLY OIL STAINED DRILLING MUD.

Lease and Well No. Charles MOORE #1 34 7S 24W

Formation Test No. 1

LEASE Charles MOORE WELL NO. 1 TEST NO. 1 TICKET NO. 10745


TOTAL DEPTH 3760

PACKER DEPTH 3728

BT. NO. 2162 DEPTH 3755

REMARKS _____

SPECIAL PRESSURE DATA



Tool Open: 1st Flow hr. 30 mins: Shut-in Initial hr. 30 min: 2nd Flow hr. 30 min: Shut-in Final hr. 30 min.

	Field Reading	Corrected Reading
(A) Initial Hydrostatic Pressure	<u>2136</u>	<u>2084</u>
(B) Initial 1st Flow Pressure	<u>35</u>	<u>43</u>
(C) Final 1st Flow Pressure	<u>43</u>	<u>52</u>
(D) Initial Shut-in Pressure	<u>969</u>	<u>986</u>
(E) Initial 2nd Flow Pressure	<u>43</u>	<u>69</u>
(F) Final 2nd Flow Pressure	<u>52</u>	<u>78</u>
(G) Final Shut-in Pressure	<u>951</u>	<u>965</u>
(H) Final Hydrostatic Pressure	<u>2084</u>	<u>2058</u>

10745